

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-065-22,253-
LEASE NAME Barnett
WELL NUMBER 1-25
SPOT LOCATION SW/4 NW/4 NE/4
SEC. 25 TWP. 7S RGE. 25W (W) (W)
COUNTY Graham
Date Well Completed 10/31/85
Plugging Commenced 10/31/85
Plugging Completed 10/31/85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR BHP Petroleum (Americas) Inc.
ADDRESS 925 Patton Road, Great Bend, Ks. 67530

PHONE # (316) 792-2756 OPERATORS LICENSE NO. 4655

Character of Well D & A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays, Ks. 67601 - Carl Goodrow

Is ACO-1 filed? yes If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 3,970'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	253.96'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

1st Plug @ 2150' w/25 sx cement; 2nd Plug @ 1300' w/100 sx cement & 1 sx bulls;
3rd Plug @ 265' w/20 sx cement; Bridge Plug @ 40' to 0 w/10 sx cement;
15 sx cement in rathole (Plugs calculated by displacement)
170 sx 60/40 Pozmix, 6% Gel, 3%CC

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Red Tiger Drilling Company License No. 5302
Address 1720 KSB Building, Wichita, Kansas 67202

STATE OF Kansas COUNTY OF Barton, ss.

Jim W. Sullivan (employee of operator) or
(operator) of above-described well, being first duly sworn on oath, says: That
I have knowledge of the facts, statements, and matters herein contained and
the log of the above-described well as filed that the same are true and
correct, so help me God.

DEC 23 1985

(Signature) Jim W. Sullivan

(Address) 925 Patton Road
Great Bend, KS 67530

SUBSCRIBED AND SWORN TO before me this 23rd day of December, 1985

Ronald E. Javel
Notary Public

My Commission expires: My Appt. Exp. Sept. 9, 1987