


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Graham County Sec. 25 Twp. 7S Rge. 25 ~~XX~~/W  
Location as "NE/CNW/SW" or footage from lines  
SW NW NW

Lease Owner Griggs Oil, Inc.  
Lease Name Richmeier Well No. #1  
Office Address 1625 KSB & T Building  
125 N Market Wichita, Kansas 67202  
Character of Well (Completed as Oil, Gas or Dry Hole)  
Dry Hole



locate well correctly  
on above  
Section Plot

Date Well completed December 19, 19 80  
Application for plugging filed December 19, 19 80  
Application for plugging approved December 19, 19 80  
Plugging commenced December 19, 4:30 A.M. 19 80  
Plugging completed December 19, 6:00 A.M. 19 80  
Reason for abandonment of well or producing formation  
No Commercial Production

If a producing well is abandoned, date of last production  
19

Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gil Balthazor  
Producing formation Depth to top Bottom Tl. Depth of Well  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
surface casing	common	0	346.17'	8 5/8"	346.17'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid  
was placed and the method or methods used in introducing it into the hold. If cement or other  
plugs were used, state the character of same and depth placed, from feet to  
feet for each plug set.

Plug #1 @ 1100' with 70 sxs

Plug #2 @ 340' with 20 sxs

Plug #3 @ 40' with 10 sxs

5 sxs in rathole

JAN 5 1981

CONSERVATION DIVISION  
Wichita, Kansas

1-5-81

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pioneer Drilling Company, Inc.  
308 West Mill Plainville, Kansas 67663

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jim Thatcher (employee of owner) or ~~(owner or operator)~~ of the  
above described well, being first duly sworn on oath, says: That I have knowledge of the  
facts, statements, and matters herein contained and the log of the above described well  
is filed and that the same are true and correct. So help me God.


(Signature) Jim Thatcher

(Address) 1625 KSB&T BLDG WICHITA  
KANSAS 67202

SUBSCRIBED AND SWORN TO before me this 31 day of December, 19 80

My commission expires August 25, 1984

Virginia Lee Smith  
Notary Public Virginia Lee Smith



W E L L L O G

15-065-21303-00-00

OPERATOR: Griggs Oil, Inc.

WELL NAME: Richmeier #1 LOCATION: SW NW NW 25-7S-25W

COUNTY: Graham STATE: Kansas

WELL COMMENCED: December 9, 1980 WELL COMPLETED: December 19, 1980

ELEVATION: 2512' G.R. TOTAL DEPTH: 3956'

PRODUCTION: D & A RIG NO: #4

CASING - 8 5/8": 346.17' of used 28# cemented with 190 sxs 60-40 poz 2% gel 3% cc  
plugdown @ 9:45 A.M. cement circ  
5 1/2": none

ALL MEASUREMENTS TAKEN FROM THE TOP OF ROTARY BUSHING:

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
0'	38'			
38'	355'			
355'	395'	shale		
395'	1245'	shale		
1245'	1457'	shale and sand		
1457'	1735'			
1735'	2165'	sand and shale		
2165'	2200'	Anhydrite		
2200'	2252'	shale		
2252'	2385'	shale	2345' - 1 degree	
2385'	2660'	shale		
2660'	2918'	shale and lime		
2918'	3112'	shale and lime		
3112'	3288'	shale and lime		
3288'	3450'	lime and shale		
3450'	3624'	shale and lime		
3624'	3770'	lime and shale		
3770'	3851'	lime and shale		
3851'	3876'	shale and lime		
3876'	3913'	lime	3913' - 1/4 degree	
3913'	3956'	lime		
3956'	RTD			

STATE OF KANSAS  
COUNTY OF

The undersigned hereby certifies that to the best of his knowledge and belief, the above facts are true and correct.

PIONEER DRILLING CO., INC.

By Connie J. Austin

SUBSCRIBED AND SWORN TO, BEFORE ME, This 29<sup>th</sup> day of December, 1980

Sharon Garvert  
NOTARY PUBLIC

SHARON GARVERT  
NOTARY PUBLIC  
STATE OF KANSAS  
My Appt. Expires 10/24/84

JAN 5 1981  
CONSERVATION DIVISION  
Wichita, Kansas  
1-581