

STATE OF KANSAS
STATE CORPORATION COMMISSION

15-193-20170-00-50

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Thomas County. Sec. 27 Twp. 7 S Rge. 36 N/W
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines
SE SE

Lease Owner Dane G. Hansen Trust
Lease Name Davis Well No. 1

Office Address P. O. Box 187, Logan, Kansas 67646
Character of Well (Completed as Oil, Gas or Dry Hole) _____

Dry Hole

Date Well completed Sept. 3, 1978
Application for plugging filed (verbally) Sept. 3, 1978
Application for plugging approved (verbally) Sept. 3, 1978
Plugging commenced Sept. 3, 1978
Plugging completed Sept. 3, 1978

Reason for abandonment of well or producing formation _____
No commercial quantity of oil or gas encountered


If a producing well is abandoned, date of last production
_____ 19 _____

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4921

Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above
Section Plat

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set 1st plug at 1850' with 70 sacks
2nd plug at 300' with 20 sacks
3rd plug at 40' with 10 sacks
Cemented with 50-50 posmix, 6% gel.

RECEIVED
STATE CORPORATION COMMISSION

SEP 08 1978

CONSERVATION DIVISION
Wichita, Kansas

9/8/78

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc.

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

Jack L. Partridge, Ass't. Secretary-Treasurer (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

801 Union Center, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of September, 1978.

My commission expires July 21, 1979

Sandra Richman
Notary Public.



OPERATOR: Dane G. Hansen Trust
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: Davis #1
 LOCATION: SE SE Section 27-7S-36W
 Thomas County, Kansas
 SPUD DATE: August 23, 1978
 COMPLETION DATE: September 3, 1978

0	100	Sand
100	2206	Sand & shale
2206	2450	Shale & sand
2450	2942	Shale & shells
2942	2975	Anhydrite
2975	3062	Shale & red beds
3062	4029	Shale & lime
4029	4258	Lime & shale
4258	4312	Shale & lime
4312	4450	Lime & shale
4450	4606	Shale & lime
4606	4620	Shale & lime
4620	4730	Lime
4730	4797	Shale & lime
4797	4921	Lime
	4921	Rotary Total Depth

Spud hole August 23, 1978. Drilled 350' of 12 1/4" hole. Ran 9 joints of 8-5/8" - 28# surface casing. Set at 346.63' K.B. with 235 sacks of 60-40 posmix, 3% CaCl, 2% gel. Cement did circulate. Plug was down at 7:00 p.m., August 23, 1978.

T.D. 4921'. Set first plug at 1850' with 70 sacks, second plug at 300' with 20 sacks, third plug at 40' with 10 sacks. Cemented with 50-50 posmix, 6% gel. Job was complete at 2:30 a.m., September 3, 1978. State Plugger, Leo Massey.

SAMPLE TOPS:

Anhydrite 2943' (+427)
 B/Anhydrite 2975' (+395)

RECEIVED
 STATE CORPORATION COMMISSION

SEP 08 1978

STATE OF KANSAS)
) ss
 COUNTY OF SEDGWICK)

CONSERVATION DIVISION
 Wichita, Kansas

9/8/78


Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the Davis #1, SE SE Section 27-7S-36W, Thomas County, Kansas.

ABERCROMBIE DRILLING, INC.

By Jack L. Partridge
 Jack L. Partridge,
 Assistant Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for the county and state aforesaid, as of this 7th day of September, 1978.

Sandra Richman
 Sandra Richman, Notary Public



My commission expires July 21, 1979.