


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

15-193-00021-00-00
WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Thomas County. Sec. 34 Twp. 7 Rge. 36 (E) (W)

Location as "NE/CNW/SW" or footage from lines SW SW SE
Lease Owner National Cooperative Refinery Association
Lease Name Wright Well No. 1
Office Address 305 Rule Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed October 9, 19 56
Application for plugging filed October 9, 19 56
Application for plugging approved October 10, 19 56
Plugging commenced October 9, 19 56
Plugging completed October 9, 19 56
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19 _____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5070 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	277'	None-Cemented

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.
Mudded hole to 270', set bridge with 1/3 sack hulls and 20 sacks of cement. Mudded hole to 35', set bridge with 1/3 sack of hulls plus 10 sacks of cement. Filled on up to base of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Bennett and Roberts Drilling, Inc.
Address Russell, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
C. R. Sears (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. R. Sears (C. R. Sears)

305 Rule Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 11th day of October, 1956

Nell McComb

My commission expires November 26, 1956.

Notary Public.

Nell McComb

PLUGGING
FILE SEC. 34 T. 7 R. 36W
BOOK PAGE 106 LINE 52

OCT 12 1956
WICHITA, KANSAS

10/12/56

15-193-00021-00-00

National Cooperative Refinery Ass'n
Wright #1

SW SW SE of Sec. 34-7-36W
Thomas County, Kansas

R.T.D. 5070'

8 5/8" Set @ 277' w/200 sx. cmt.

Commenced 9/15/56
Completed 10/9/56

Contractor: Bennett & Roberts Drilling, Inc.

----- Figures Indicate Bottom of Formation -----

Surface soil and clay	20
Clay & gumbo	70
Sand & Gravel	235
Shale	855
Shale & Shells	1275
Sand	1340
Shale & Shellix	1810
Shale, Lime, Pyrite streaks	1840
Shale & Shells	2330
Anhydrite	2350
Red Bed & Shale	2923
Anhydrite	2955
Shale & Shells	3107
Shale, Shells & Red Bed	3245
Lime	3309
Shale & Lime	4142
Lime	4175
Lime & Shale	4218
Lime	4471
Shale & Lime	4473
Lime	4565
Lime & Shale	4659
Lime	4700
Lime & Shale	4848
Sand	4850
Lime	4861
Lime & Shale	4899
Lime	4978
Cherty Lime	5070
Lime	5070
Cherty Lime	5070

RECEIVED
STATE CORPORATION COMMISSION
5070

OCT 12 1956

10/12/56

CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
RUSSELL COUNTY) SS.

I hereby certify that the above information is true and correct to the best of my knowledge.

BENNETT & ROBERTS DRILLING, INC.

By B. J. Baker

Subscribed and sworn to before me this 10th day of October, 1956.

W. J. Hummel
Notary Public

My Commission Expires 6/17/58

PLUGGING
FILE SEC 34 T. 7 R. 36 W
BOOK PAGE 106 LINE 52