

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-193-20218-00-02

LEASE NAME Lehman #1

WELL NUMBER _____

SPOT LOCATION C SW NE NW

SEC. 35 TWP. 7s RGE. 36w or (W)

COUNTY Thomas

Date Well Completed _____

Plugging Commenced 4/11/84

Plugging Completed 4/17/84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR A.L. Abercrombie, Inc.

ADDRESS 801 Union Center, Wichita, Ks. 67202

PHONE # 316 262-1841 OPERATORS LICENSE NO. #5393

Character of Well _____
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 4926'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put In | Pulled out |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8 5/8 | 367' | none |
| | | | | 4 1/2" | 4921' | 2224' |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Ran 4 sacks cement, sand to 4650' & 4 sacks cement. Shot pipe at 3510', 3004', 2506', 2378', & 2224'. Pulled total of 54 joints. Plugged well with 2 hulls, 1 hull with 8 gel, 100 cement, 32 gel, released plug & 70 sacks 50/50 poz 10% gel 3% c.e.

Plugging complete

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050

Address Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 24th day of April, 1984



Irene Hoover
Notary Public

RECEIVED
STATE CORPORATION COMMISSION

APR 26 1984

CONSERVATION DIVISION
Wichita, Kansas