

R

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15-062-20818-00-00 (of this well)

MAY 30 1979
523-29
DIVISION

Operator's Full Name F & M Oil Co. Inc.

Complete Address 505 Union Center, Wichita, Ks.

Lease Name Dugan Well No. 1

Location SW-SE-SE Sec. 3 Twp. 7 Rge. 25 (E) (W) X

County Graham Total Depth 3905

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated _____

Plugging Contractor Kelso Casing Pulling

Address Box 174, Chase Ks License No. 683

Operation Completed: Hour 10:30 AM Day 23 Month May Year 1979

The above well was plugged as follows:

KB, 2509, Dak Top, 1500' ST, 250' of 8 5/8" cwe, 160 sx,
4 1/2" casing set @ 3907 w/125. sx. Plug. Back, 3830,
Perf. 3966 to 3772. Bottom Plug to 3600 w/sand + 4.5x Cem,
Recovered 1627' of 4 1/2" Pumped down. J.P.
3 sx. Hulls, 70. sx cem. 5/8" Por 6% Gel. 11. sx Gel.
Release Plug + 60 " " " " Max. Pres. 400 lbs.
Shut in Pres. 200 lbs.

Commented By Allied

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 5-30-79

INV. NO. 9708-W

Signed: [Signature]
Well Plugging Supervisor