

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-065 20308-00-00

RECEIVED
STATE CORPORATION COMMISSION
FEB 26 1970
CONSERVATION DIVISION
Wichita, Kansas
2-26-70

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Murfin Drilling Company,

Complete Address 617 Union Center Building, Wichita, Kansas.

Lease Name Lindenman Well No. 1

Location CS/2-NE-NW Sec. 7 Twp. 7 Rge. (E) (W) 25

County Graham Total Depth 3905'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Above

Address License No.

Operation Completed: Hour 12:00 PM Day 24 Month 2 Year 1970

The above well was plugged as follows:

295'--8 5/8" Surface casing, cement circulated.
Top of Dakota section @ 1050'.

Circulated hole with heavy mud. Pulled DP to 1275' and displaced 100 Sx. cement thru
DP from 1275' to 950'. Pulled DP to 310' and displaced 25 Sx. cement thru DP from
310' to 235'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: N. L. Nichols
Well Plugging Supervisor

DATE 2/27/70

INV. NO. 1505-W