

KANSAS

Form CP-3
Rev. 6-9-67

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-065-20097-00-00

10-23-1967
10-22-67
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Paine Drilling Company, Incorporated,
Complete Address Box "D", Hill City, Kansas.
Lease Name Wilcox Well No. 2
Location SW-SE-NW Sec. 7 Twp. 7 Rge. (E) (W) 25
County Graham Total Depth 3835'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Above

Address License No.
Operation Completed: Hour 8:00PM Day 18 Month 10 Year 1967

The above well was plugged as follows:

238'--7" Od Surface pipe, cement circulated with 125 Sx. (6 1/4" hole)
Dakota section from 970' to 800'.

Circulated hole with heavy mud. Pulled DP to 990' and displaced 55 Sx. cement thru
DP from 990' to 690'. Pulled DP to 270' and displaced 15 Sx. cement thru DP from
270' to 195'. Pulled DP, set bridge @ 40' and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 10/23/67
INV. NO. 6549-W