

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-065-30133-00-00

RECEIVED
OCT 23 1967
10-22-67
CONSERVATION DIVISION
WICHITA, KANSAS

Operator's Full Name Paine Drilling Company, Incorporated.

Complete Address Box "D", Hill City, Kansas.

Lease Name Wilcox Well No. 1

Location NE-SE-NW Sec. 7 Twp. 7 Rge. (E) (W) 25

County Graham Total Depth 3860'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated (Temporarily abandoned by Halliburton Oil Producing Co. 12/16/65, lease later acquired by Paine Drlg. Co. Inc.).

Plugging Contractor Halliburton Company

Address Box # 296, Hill City, Kansas. License No.

Operation Completed: Hour 9:15PM Day 18 Month 10 Year 1967

The above well was plugged as follows:

256'--7" OD Surface casing, cement circulated with 125 Sx. (6 1/4" hole)
Dakota section from 970' to 800'. (Well has been periodically filled with drilling mud)

Squeezed well with 55 Sx. cement plus 6% gel from 990 to 690', followed with 17 Bbls.
fresh rotary mud from 690' to 270' then 15 Sx. cement from 270' to 195'. Mud from
195' to 35' (7 Bbls.). Cement from 335' to bottom of cellar with 10 Sx. Maximum
pump-in pressure 250#, Final shut-in pressure 150#.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Pichele
Well Plugging Supervisor

DATE 10/23/67
INV. NO. 6546-W

15-065-30133-00-00

CONTRACTOR'S WELL LOG

COMPANY:
CONTRACTOR:
WELL:
LOCATION:

COMMENCED:
COMPLETED:

HALLIBURTON OIL PRODUCING CO.
PAINE DRILLING CO., INC.
WILCOX # 1
NE SE NW Sec. 7-7-23W
Graham County, Kansas
DECEMBER 8, 1965
DECEMBER 16, 1965

0	258	Surface Soils
258	1 1000	Sand & Shale
1000	11475	Shale & Sand
11475	1910	Shale & Shells
1910	2128	Shale
2128	2161	Andhydrite
2161	2485	Shale
2485	2805	Shale & Lime
2805	2963	Lime & Shale
2963	3060	Lime
3060	3122	Shale & Lime
3122	3185	Lime
3185	3285	Lime & Shale
3285	3540	Shale & Lime
3540	3645	Lime & Shale
3645	3835	Lime

RECEIVED
OCT 28 1967
10-22-67
OIL & GAS DIVISION
Tulsa, Kansas

SET 7" SURFACE PIPE AT 258' W/~~SACKS~~ 125 SACKS CEMENT

~~XXXX~~ TEMPORARY ABANDONED

WE HEREBY CERTIFY THAT THE ABOVE IS A CORRECT AND ACCURATE LOG OF THE ABOVE MENTIONED WELL, AS SHOWN ON THE DAILY DRILLING REPORTS.

PAINE DRILLING CO., INC.

BY: Louis Edgett
BOOKKEEPER

SUBSCRIBED AND SWORN TO BEFORE ME THIS 22th DAY OF OCTOBER, 1967.

My Commission Expires January 20, 1968

Lois Peller
NOTARY PUBLIC