

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

15-065-20281-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 2 1969  
CONSERVATION DIVISION  
Wichita, Kansas

12-2-69

Operator's Full Name Brandt-Clark Oil Company,

Complete Address 505 First National Bank Building, Wichita, Kansas.

Lease Name Goddard Well No. 1

Location CSE-NW-SE Sec. 16 Twp. 7 Rge. (E) (W) 25

County Graham Total Depth 3980'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor H-30 Drilling, Incorporated.

Address 200 North Main, Wichita, Kansas. License No.       

Operation Completed: Hour 2:30 PM Day 28 Month 11 Year 1969

The above well was plugged as follows:

250'--8 5/8" Surface casing, cement circulated with 175 Sx.  
Top of Dakota section @ 1060'.

Circulated hole with heavy mud. Pulled DP to 1300' and displaced 100 Sx. cement thru  
DP from 1300' to 975'. Pulled DP to 275' and displaced 25 Sx. cement thru DP from  
275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. Nichols  
Well Plugging Supervisor

DATE 12/2/69

INV. NO. 950-W