

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-065-01310-00-00

RECEIVED
STATE CORPORATION COMMISSION
DEC 8 - 1970
CONSERVATION DIVISION
Wichita, Kansas
12-8-70

Operator's Full Name Glen W. Peel,

Complete Address R. R. #3, Box #144-B, Wichita, Kansas.

Lease Name Lindenman Well No. B-1

Location CN/2-N/2-NE Sec. 6 Twp. 7 Rge. (E) (W) 25

County Graham Total Depth 3850'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Southwest Casing Pulling Company, Incorporated,

Address Box #364, Great Bend, Kansas. License No. 399

Operation Completed: Hour 5:00 PM Day 3 Month 12 Year 1970

The above well was plugged as follows:

287'--8 5/8" Surface casing, cement circulated with 185 Sx.
3846'--5 1/2" Production casing cemented on bottom with 125 Sx. Well Plugged back to 3710'. Top perforations from 3704' to 3707'.

Sanded well back to 3675' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing and squeezed well initially with 5 sacks hulls and 8 sacks gel and followed with 100 Sx. cement from 1300' to 975', then 17 sacks gel from 975' to 300' and followed with 25 Sx. cement from 300' to 225' then 5 sacks gel from 225' to 30' and finally 10 Sx. cement from 30' to bottom of cellar. Maximum pump-in pressure-375#. Final shut-in pressure-200#. (Mudding and cementing operations performed by Halliburton).

I hereby certify that the above well was plugged as herein stated.

NOTICED
DATE 12/8/70
INV. NO. 3019-W

Signed: M. L. Pichek
Well Plugging Supervisor