

CONFIDENTIAL

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

KCC

MAY 27 2003

Form ACO-1
September 1999
Form Must Be Typed

WELL COMPLETION FORM
WELL HISTORY - DESCRIPTION OF WELL & LEASE
ORIGINAL

Operator: License # 4058
Name: American warrior INC
Address: P.O.Box 399
City/State/Zip: Garden City, KS, 67846
Purchaser: NONE

Operator Contact Person: Kevin wiles SR
Phone: (620) 275-2963

Contractor: Name: Cheyenne Drilling
License: 5382

Wellsite Geologist: NONE

Designate Type of Completion:
 New Well Re-Entry Workover
 Oil SWD SIOW Temp. Abd.
 Gas ENHR SIGW
 Dry Other (Core, WSW, Expl., Cathodic, etc)

If Workover/Re-entry: Old Well Info as follows:

Operator: _____
Well Name: _____

Original Comp. Date: _____ Original Total Depth: _____

Deepening Re-perf. Conv. to Enhr./SWD
 Plug Back Plug Back Total Depth

Commingled Docket No. _____

Dual Completion Docket No. _____

Other (SWD or Enhr.?) Docket No. _____

| | | |
|-----------------------------------|-----------------|---|
| <u>3-15-03</u> | <u>3-21-03</u> | <u>4-16-03</u> |
| Spud Date or Recompletion Date | Date Reached TD | Completion Date or Recompletion Date |

API No. 15 - 055-21,802-00-00

County: Finney 125's & 145'W of

C E/2. Nw. NE Sec. 33 Twp. 23s S. R. 32 East West

785 feet from S / (N) (circle one) Line of Section

1795 feet from (E) / W (circle one) Line of Section

Footages Calculated from Nearest Outside Section Corner:

(circle one) NE SE NW SW

Lease Name: Neeley Well #: 5

Field Name: congdon

Producing Formation: Morrow

Elevation: Ground: 2830' Kelly Bushing: 2835

Total Depth: 4900 Plug Back Total Depth: 4865

Amount of Surface Pipe Set and Cemented at 552' Feet

Multiple Stage Cementing Collar Used? Yes No

If yes, show depth set DV.Tool@2770' Feet

If Alternate II completion, cement circulated from 2770'

feet depth to Surface w/ 400sks sx cmt.

Drilling Fluid Management Plan UW 7-15-03
(Data must be collected from the Reserve Pit)

Chloride content 11000 ppm Fluid volume 300 bbls

Dewatering method used Evaporation

Location of fluid disposal if hauled offsite: _____

Operator Name: _____

Lease Name: _____ License No.: _____

Quarter _____ Sec. _____ Twp. _____ S. _____ East West

County: _____ Docket No.: _____

RELEASED
FROM
CONFIDENTIAL

INSTRUCTIONS: An original and two copies of this form shall be filed with the Kansas Corporation Commission, 130 S. Market - Room 2078, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information of side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Signature: [Signature]

Title: Production Supt Date: 5-27-2003

Subscribed and sworn to before me this 27th day of May, 19 2003

Notary Public: [Signature]

Date Commission Expires: 11-7-03

Notary Public State of Kansas
My Appt. Expires 11-7-03

KCC Office Use ONLY

- Letter of Confidentiality Attached
If Denied, Yes Date: _____
- Wireline Log Received
- Geologist Report Received
- IC Distribution

KCC

Side Two

CONFIDENTIAL

MAY 27 2003

Operator Name: American warrior INC Lease Name: Neeley Well #: 5
Sec. 33 Twp. 23s S. R. 32 County: Finney 125's & 145'W of

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all final copies of drill stems tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface test, along with final chart(s). Attach extra sheet if more space is needed. Attach copy of all Electric Wireline Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken (Attach Additional Sheets)
Samples Sent to Geological Survey
Cores Taken
Electric Log Run (Submit Copy)
List All E. Logs Run:
Cased Hole only, Gamma ray Nuetron
Log Formation (Top), Depth and Datum
Name Top Datum
Surface hole 0-555'
Sandstone & clay 555'-1681'
Red Bed 1681-2547'
Limestone & Shale 2547'-4900'

CASING RECORD New Used
Report all strings set-conductor, surface, intermediate, production, etc.
Table with columns: Purpose of String, Size Hole Drilled, Size Casing Set (In O.D.), Weight Lbs. / Ft., Setting Depth, Type of Cement, # Sacks Used, Type and Percent Additives

ADDITIONAL CEMENTING / SQUEEZE RECORD
Table with columns: Purpose, Depth Top Bottom, Type of Cement, #Sacks Used, Type and Percent Additives

PERFORATION RECORD - Bridge Plugs Set/Type Specify Footage of Each Interval Perforated
Acid, Fracture, Shot, Cement Squeeze Record (Amount and Kind of Material Used) Depth
4 4680-4688, 4697-4712 1500 gals 20%acid, 18,500 #s 20/40 sand
in Cross-linker gel
RELEASED FROM CONFIDENTIAL

TUBING RECORD Size Set At Packer At Liner Run Yes No
2-3/8" coated 4650' 4653'
Date of First, Resumed Production, SWD or Enhr. Producing Method Flowing Pumping Gas Lift Other (Explain)
SI
Estimated Production Per 24 Hours Oil Bbls. Gas Mcf Water Bbls. Gas-Oil Ratio Gravity
NONE NONE SI

Disposition of Gas METHOD OF COMPLETION Production Interval
Vented Sold Used on Lease Open Hole Perf. Dually Comp. Commingled
Other (Specify)

ALLIED CEMENTING CO., INC. 11975

Federal Tax I.D. # [REDACTED]

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:

Co. #1111

| | | | | | | | |
|-------------------------|--------|---|-------------------|------------|----------------------------|--------------------------|---------------------------|
| DATE <i>7/15/02</i> | SEC | TWP | RANGE <i>32.4</i> | CALLED OUT | ON LOCATION <i>3:15 PM</i> | JOB START <i>5:25 AM</i> | JOB FINISH <i>5:50 PM</i> |
| LEASE <i>Woolley</i> | WELL # | LOCATION <i>1000 S. 2nd St. Rd 2000</i> | | | COUNTY <i>Woolley</i> | STATE <i>KS</i> | |
| OLD OR NEW (Circle one) | | | | | KCC | | |

CONTRACTOR *Woolley*

TYPE OF JOB *Oil Field*

HOLE SIZE *12 1/4* T.D. *555*

CASING SIZE *24"* DEPTH *560*

TUBING SIZE DEPTH

DRILL PIPE DEPTH

TOOL DEPTH

PRES. MAX *150* MINIMUM *10*

MEAS. LINE SHOE JOINT *45*

CEMENT LEFT IN CSG.

PERFS.

DISPLACEMENT *32,400 B/L*

OWNER *Woolley* **MAY 27 2003**

| | | |
|-----------------|------------------------|-------------------------|
| CEMENT | CONFIDENTIAL | |
| AMOUNT ORDERED | <i>350 lbs. Cement</i> | |
| COMMON | <i>210 @</i> | <i>7.55 = 1648.50</i> |
| POZMIX | <i>140 @</i> | <i>3.55 = 497.00</i> |
| GEL | <i>6 @</i> | <i>100.00 = 600.00</i> |
| CHLORIDE | <i>11 @</i> | <i>20.00 = 220.00</i> |
| <i>Pl. Seal</i> | <i>4 @</i> | <i>1.40 = 5.60</i> |
| HANDLING | <i>350 @</i> | <i>1.10 = 385.00</i> |
| MILEAGE | <i>471 @</i> | <i>45.00 = 21195.00</i> |
| | | TOTAL 4623.70 |

EQUIPMENT

PUMP TRUCK CEMENTER *Max*

300 HELPER *Woolley*

BULK TRUCK DRIVER *Jim*

DRIVER

RELEASED FROM CONFIDENTIAL

REMARKS: SERVICE

Oil Field Cement Co. #1111 2000

1000 S. 2nd St. Rd 2000

Woolley, KS

Woolley, KS

Woolley, KS

| | | |
|-------------------|--------------|----------------------|
| DEPTH OF JOB | <i>550'</i> | |
| PUMP TRUCK CHARGE | | <i>520.00</i> |
| EXTRA FOOTAGE | <i>250 @</i> | <i>.50 = 125.00</i> |
| MILEAGE | <i>70 @</i> | <i>3.00 = 210.00</i> |
| PLUG | <i>1 @</i> | <i>45.00 = 45.00</i> |
| | | TOTAL 900.00 |

CHARGE TO: *American Warrior Co.*

STREET _____

CITY _____ STATE _____ ZIP _____

FLOAT EQUIPMENT

| | |
|--------------------|--------------|
| <i>1 @</i> | <i>45.00</i> |
| <i>1 @</i> | |
| <i>1 @</i> | |
| <i>1 @</i> | |
| <i>1 @</i> | |
| TOTAL 45.00 | |

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

| | |
|--------------|----------------|
| TAX | |
| TOTAL CHARGE | <i>4965.70</i> |
| DISCOUNT | <i>496.87</i> |
| | <i>4471.83</i> |

IF PAID IN 30 DAYS

SIGNATURE: *Paul Ford*

PRINTED NAME

DRILLER'S LOG

AMERICAN WARRIOR, INC.
NEELEY #5
SECTION 33-T23S-R32W
FINNEY COUNTY, KANSAS

CONFIDENTIAL

COMMENCED: 03-15-03
COMPLETED: 03-21-03

RECEIVED
MAY 29 2003
KCC WICHITA

SURFACE CASING: 552' OF 8 5/8" CMTD
W/350 SKS 60:40 POZ + 2% GEL + 1/4#/SK
FLOCELE.

FORMATION

DEPTH

RELEASED


SURFACE HOLE
SANDSTONE & CLAY
RED BED
LIMESTONE & SHALE

0 - 555
555 - 1681
1681 - 2547
2547 - 4900 RTD

FROM
CONFIDENTIAL

I DO HEREBY CERTIFY THAT THE FOREGOING STATEMENTS ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

CHEYENNE DRILLING, INC.




WRAY VALENTINE

STATE OF KANSAS: ss:

SUBSCRIBED AND SWORN TO BEFORE ME THIS 21ST DAY OF MARCH, 2003.

JOLENE K. RUSSELL


NOTARY PUBLIC


JOLENE K. RUSSELL
Notary Public - State of Kansas
My Appt. Expires 9-13-03

KCC
MAY 27 2003
CONFIDENTIAL

JOB LOG

SWIFT Services, Inc.

DATE **3-20-03** PAGE NO. **1**

CUSTOMER **AMERRA WARRIOR** WELL NO. **#5** LEASE **WEELEY** JOB TYPE **5 1/2" 2-STAGE LONGSTRECH** TICKET NO. **5360**

| CHART NO. | TIME | RATE (BPM) | VOLUME (BBL)(GAL) | PUMPS | | PRESSURE (PSI) | | DESCRIPTION OF OPERATION AND MATERIALS |
|-----------|------|------------|-------------------|-------|---|--------------------|--------|--|
| | | | | T | C | TUBING | CASING | |
| | 2000 | | | | | | | ON LOCATION |
| | 2330 | | | | | | | START 5 1/2" CASING IN WELL |
| | | | | | | | | KCO |
| | | | | | | | | TD-4900' 5 1/2-15.5 #/FT |
| | | | | | | | | TD-4900' SET @ 4898' |
| | | | | | | | | SI-24' |
| | | | | | | | | CONFIDENTIAL |
| | | | | | | | | CONNECTIONS - 2, 6, 8, 10, 51, 77, 98 |
| | | | | | | | | BASKETS - 3, 52, 78, 99 |
| | | | | | | | | DV TOOL @ 2770 TOP JT # 52 |
| | 0230 | | | | | | | DROP BALL - BREAK CIRCULATION |
| | 0255 | 6 | 5-20-3 | | ✓ | 500 | | WATER SPACER / 850 GAL FLOCHER / WATER SPACER |
| | 0300 | 6 | 10 | | ✓ | 500 | | KCL WATER SPACER |
| | 0310 | 6 | 51.3 | | ✓ | 400 | | MIX 150 SWS SMC @ 13.0 PPG |
| | | | | | | | | WASH OUT PUMP - LEDES - RELEASE 1ST STAGE PLUG |
| | 0325 | 6 1/2 | 0 | | ✓ | 800 ^{MAX} | | DISPLACE PLUG (50H20 - 66 min) |
| | 0345 | 5 | 116 | | | 1200 | | PLUG DOWN |
| | 0350 | | | | | OK | | RELEASE PST - HELD |
| | 0355 | | | | | | | DROP DV OPENING PLUG |
| | 0430 | | | | ✓ | 1200 | | OPN DV TOOL - CIRCULATE WELL |
| | 0500 | 6 | 10 | | ✓ | 300 | | KCL WATER SPACER |
| | 0505 | 6 | 230 | | ✓ | 200 | | MIX 400 SWS SMC @ 11.1 PPG |
| | 0555 | | | | | | | WASH OUT PUMP - LEDES - RELEASE CLOSING PLUG |
| | 0600 | 6 1/2 | 0 | | ✓ | | | DISPLACE PLUG |
| | 0610 | | 66 | | | 800 | | PLUG DOWN |
| | 0615 | | | | | 1800 | | SET UP - CLOSE DV TOOL |
| | | | | | | OK | | RELEASE PST - HELD |
| | | | | | | | | CIRCULATE <u>75</u> SWS COMET TO PST |
| | | | | | | | | WASH UP |
| | 0700 | | | | | | | JOB COMPLETE |
| | | | | | | | | THANK YOU |
| | | | | | | | | WABE, DUSTY SHAVE, NICK |



CHARGE TO:
AMERICAN WARRIOR INC.
 ADDRESS:
 CITY, STATE, ZIP CODE:

TICKET
 No. **5360**

PAGE **1** OF **1**

SERVICE LOCATIONS
 1. **NESS CITY, KS**
 2.
 3.
 4.
 REFERRAL LOCATION

WELL/PROJECT NO. # **5**
 LEASE **NEELEY**
 COUNTY/PARISH **FINNEY**
 STATE **KS**
 CITY
 DATE **3-20-03**
 OWNER **SAME**

TICKET TYPE SERVICE SALES
 CONTRACTOR **CHRYSLER DRILLING**
 RIG NAME/NO.
 SHIPPED VIA **CT**
 DELIVERED TO **LOCATION**
 ORDER NO.

WELL TYPE **INJECTION**
 WELL CATEGORY **DEVELOPMENT**
 JOB PURPOSE **5 1/2" 2-STAGE LONG-STRING**
 WELL PERMIT NO.
 WELL LOCATION **GARDEN CITY, KS - E EDGE, 2nd 1/2w**

INVOICE INSTRUCTIONS


| PRICE REFERENCE | SECONDARY REFERENCE/ PART NUMBER | ACCOUNTING | | | DESCRIPTION | QTY. | | U/M | | UNIT PRICE | AMOUNT |
|-----------------|-------------------------------------|------------|------|----|--------------------------------|-------|--------|-----|--------|------------|---------|
| | | LOC | ACCT | DF | | | | | | | |
| 575 | RECEIVED | 1 | | | MILEAGE # 104 | 60 | | MI | | 2.50 | 150.00 |
| 579 | | 1 | | | PUMP SERVICE 2-STAGE | 1 | 1900 | JOB | FR | 1500.00 | 1500.00 |
| 221 | MAY 29 2003 | 1 | | | LIQUID KCI | 2 | | GAL | | 19.00 | 38.00 |
| 280 | KCC WICHITA | 1 | | | FLOCHER 21 | 850 | | GAL | | 1.50 | 1275.00 |
| 407 | | 1 | | | INSERT FLOAT SHOE W/ FOLLOW UP | 1 | | EA | 5 1/2" | 230.00 | 230.00 |
| 402 | | 1 | | | CENTRALIZERS | 7 | | EA | | 44.00 | 308.00 |
| 403 | | 1 | | | CONCRETE BASKETS | 4 | | EA | | 125.00 | 500.00 |
| 408 | | 1 | | | DU TOOL - PLUG SET TOP JT # 52 | 1 | 2770 | EA | FR | 2150.00 | 2150.00 |
| 330 | | 1 | | | SWIFT MULTI-DRIFT STAMPER | 550 | | SKS | | 9.75 | 5362.50 |
| 276 | | 1 | | | FLOPPE | 138 | | URS | | 90 | 124.20 |
| 581 | | 1 | | | SERVICE CLAMP CONJCT | 550 | | SKS | | 1.00 | 550.00 |
| 583 | | 1 | | | DRYAGE | 54688 | 164064 | URS | M | 85 | 1394.54 |

RELEASED FROM CONFIDENTIAL

KCC
 MAY 27 2003
 CONFIDENTIAL

LEGAL TERMS: Customer hereby acknowledges and agrees to the terms and conditions on the reverse side hereof which include, but are not limited to, **PAYMENT, RELEASE, INDEMNITY, and LIMITED WARRANTY** provisions.

MUST BE SIGNED BY CUSTOMER OR CUSTOMER'S AGENT PRIOR TO START OF WORK OR DELIVERY OF GOODS

X 
 DATE SIGNED **3-20-03** TIME SIGNED **2:00**
 A.M. P.M.

REMIT PAYMENT TO:
SWIFT SERVICES, INC.
P.O. BOX 466
NESS CITY, KS 67560
785-798-2300

| SURVEY | AGREE | UN-DECIDED | DIS-AGREE | PAGE TOTAL |
|---|-------|------------|-----------|------------|
| OUR EQUIPMENT PERFORMED WITHOUT BREAKDOWN? | | | | 13582.24 |
| WE UNDERSTOOD AND MET YOUR NEEDS? | | | | |
| OUR SERVICE WAS PERFORMED WITHOUT DELAY? | | | | |
| WE OPERATED THE EQUIPMENT AND PERFORMED JOB CALCULATIONS SATISFACTORILY? | | | | TAX |
| ARE YOU SATISFIED WITH OUR SERVICE? <input type="checkbox"/> YES <input type="checkbox"/> NO | | | | TOTAL |
| <input type="checkbox"/> CUSTOMER DID NOT WISH TO RESPOND | | | | |

CUSTOMER ACCEPTANCE OF MATERIALS AND SERVICES - The customer hereby acknowledges receipt of the materials and services listed on this ticket.

SWIFT OPERATOR **Wayne Wilson** APPROVAL

Thank You!