


15-179-00184-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

SHERIDAN County. Sec. 15 Twp. 7 Rge. (E) 28 (W)  
Location as "NE/CNW/SW" or footage from lines SESESW  
Lease Owner THEODORE GORE  
Lease Name WATKINS Well No. 1  
Office Address 400 BROWN BUILDING WICHITA, KANSAS  
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE  
Date well completed JUNE 11, 1957 19  
Application for plugging filed JUNE 11, 1957 19  
Application for plugging approved JUNE 11, 1957 19  
Plugging commenced JUNE 11, 1957 19  
Plugging completed JUNE 11, 1957 19  
Reason for abandonment of well or producing formation DRY HOLE

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well ELDON PETTY  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4550' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
SURFACE		0	274'	8 5/8"	274	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

HEAVY MUD TO 275' SET PLUG 1/2 SACK HULLS AND 20 SACKS CEMENT FILLED HOLE TO 40'  
SET PLUG 1/2 SACK HULLS AND 10 SACKS CEMENT

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor EMPIRE DRILLING COMPANY  
Address 400 BROWN BUILDING WICHITA, KANSAS

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
I, THEODORE GORE, (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God!

(Signature) Therese Gore  
400 BROWN BUILDING WICHITA, KANSAS  
(Address)

SUBSCRIBED AND SWORN TO before me this 20TH day of JUNE, 19 57

My commission expires JULY 2, 1958

Hazel P. Pearson  
HAZEL PIERSON Notary Public.

PLUGGING  
FILE SEC 15 T 7 28W  
BOOK PAGE 21 LINE 5

JUN 25 1957  
JUN 25 1957  
CONSERVATION DIVISION  
Wichita, Kansas

## LOG

COMPANY: THEODORE GORE, WICHITA, KANSAS

FARM: WATKINS NO 1

CONTRACTOR: EMPIRE DRILLING COMPANY, WICHITA, KANSAS

LOCATION: SE SE SW SEC 15-7-28W SHERIDAN COUNTY, KANSAS

COMMENCED: MAY 30, 1957

ELEVATION: 2785 KB

COMPLETED: JUNE 11, 1957

0	TO	250	SAND AND SHALE
250	TO	305	SHALE
305	TO	1590	SHALE AND SHELLS
1590	TO	2025	SAND-SHALE-SHELLS
2025	TO	2493	SHALE AND SHELLS
2493	TO	2536	ANHYDRITE
2536	TO	2890	SHALE AND SHELLS
2890	TO	3395	SHALE AND LIME
3395	TO	3455	LIME AND SHALE
3455	TO	3575	SHALE AND LIME
3575	TO	3950	LIME AND SHALE
3950	TO	4247	LIME
4247	TO	4295	SHALE AND LIME
4295	TO	4480	SHALE
4480	TO	4507	SHALE AND CHERT
4507	TO	4550	LIME AND CHERT
		4550	RTD O&A

RAN: 8 5/8" SET WITH 125 SACKS CEMENT AT 282'

TOPS:	TOPEKA	3731
	HEEBNER	3920
	TORONTO	3945
	LANSING KANSAS CITY	3962
	BASE KANSAS CITY	4185
	MISSISSIPPIAN	4496


I, DAN J. KORNFELD, DO HEREBY CERTIFY THAT THE ABOVE AND FOREGOING IS A TRUE AND CORRECT COPY OF THE LOG ON THE WATKINS NO. 1 SE SE SW SEC 15-7-28W, SHERIDAN COUNTY, KANSAS AS REFLECTED BY THE FILES OF THE EMPIRE DRILLING COMPANY.

*Dan J. Kornfeld*  
DAN J. KORNFELD

SUBSCRIBED AND SWORN TO BEFORE ME, A NOTARY PUBLIC WITHIN AND FOR SEDGWICK COUNTY, KANSAS, THIS 20TH DAY OF JUNE, 1957.

*Hazel Pierson*  
HAZEL PIERSON, NOTARY PUBLIC

MY COMMISSION EXPIRES JULY 2, 1958



JUN 25, 1957  
WICHITA