

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD

Sheridan County. Sec. 2 Twp. 7S Rge. 29 (E) W (W)

Location as "NE/CNW/SW" or footage from lines SE SE SW

Lease Owner Peel-Hardman Oil Producers

Lease Name Vaughn Well No. 1

Office Address P.O. Box 359, Hoisington, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date well completed Mar. 12, 19 54

Application for plugging filed Mar. 12, 19 54

Application for plugging approved Mar. 12, 19 54

Plugging commenced Mar. 12, 19 54

Plugging completed Mar. 12, 19 54

Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well

Producing formation Depth to top Bottom Total Depth of Well 4220 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	280	8 5/8	280	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

From 4022' to 271 1/2' - heavy rotary mud
 271 1/2' to 270' - wooden plug
 270' to 224' - 15 sacks cement and 1/2 sack hulls
 224' to 41 1/2' - heavy rotary mud
 41 1/2' to 40' - wooden plug
 40' to 6' - 10 sacks cement and 1/2 sack hulls
 6' to surface - cellar

RECEIVED
 MAR 19 1954
 CONSERVATION DIVISION
 WICHITA, KANSAS

Name of Plugging Contractor Glenn W. Peel
Address P.O. Box 359, Hoisington, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
Glenn W. Peel (employee of owner) or (owner) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. GLENN W. PEEL

(Signature) BY: [Signature]
P.O. Box 359, Hoisington, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 18th day of March, 19 54

[Signature] Notary Public.

My commission expires June 4, 1955

PLUGGING
 21 7 29 W
 19 29

DRILLERS' LOG

Company: Peel-Hardman Oil Producers

Farm Name: Vaughn Well No. 1

Total Depth: 4220'.

Comm: 3-3-54 Comp: 3-12-54

Contractor: Glenn W. Peel

Casing: 8 5/8" 280' cem.

SE SE SW
Sec. 2, Twp. 7S, Rge 29W,

County: Sheridan,
Kansas

Production:

Elevation:

Figures below indicate bottoms of formations:

Surface soils	0 -	280
Shale		1030
Sand		1800
Shale		2100
Shale and shells		2400
Red bed and shale		2560
Anhydrite		2605
Shale and shells		2710
Shale and lime		2870
Shale and shells		2995
Shale and lime		3350
Lime		3605
Shale and lime		3690
Lime		3765
Lime and shale		3865
Lime		4220
Total Depth		4220

This is to certify that the above information is to the best of our knowledge, true and correct.

GLENN W. PEEL

BY: Way Herbert

SUBSCRIBED AND SWORN to be fore me this 18th day of March, 1954.

My commission expires: June 4, 1955

Mervin M. Herbert
Notary Public

RECEIVED
STATE OF KANSAS COMMISSION
MAY 10 1954
MAR 19 1954
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE NO. 217 R 29W
BOOK PAGE 19 LINE 29