


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Thomas County. Sec. 12 Twp. 7 Rge. 32 (E) W (W)
Location as "NE/CNW/SW" or footage from lines SW SW
Lease Owner Leo J. Dreiling Oil Company
Lease Name Flanagin Well No. 1
Office Address Route 2, Victoria, Kansas 67671
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 6-2 19 68
Application for plugging filed 6-2 19 68
Application for plugging approved 6-2 19 68
Plugging commenced 6-2 19 68
Plugging completed 6-2 19 68
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bill Nichols
Producing formation Depth to top Bottom Total Depth of Well Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Pipe				8 5/8"	261'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

1st. plug was set at 1685' with 70 sacks cement
2nd. plug was set at 275' with 20 sacks cement
3rd. plug was set at 40' with 10 sacks cement
Cementing to bottom of cellar

RECEIVED
STATE CORPORATION COMMISSION
JUN 4 1968 JUN 4 1968
CONSERVATION DIVISION
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor L. J. Dreiling & Sons, Inc.
Address Route 2, Victoria, Kansas 67671

STATE OF KANSAS, COUNTY OF ELLIS, ss.
I, Leo F. Dreiling

(employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leo F. Dreiling
LEO F. DREILING, ROUTE 2, VICTORIA, KANSAS 67671
(Address)



Subscribed and sworn to before me this 3rd day of June, 19 68
My commission expires September 19, 1970
JOSEPH A. HESS Notary Public

L. J. DREILING and SONS, Inc.
 VICTORIA, KANSAS

WELL LOG

Company	Leo J. Dreiling Oil Company Route 2 Victoria, Kansas	Sec. 12	Twp. 7	Rng. 32
Farm	Flanagin No. 1	Location	SW SW	
Total Depth	4278'	County	Thomas	
Comm.	5-25-68 Comp. 6-2-68	Elevation:	3034' K.B.	
Contractor	L. J. Dreiling & Sons, Inc. Route 2 Victoria, Kansas 67671		3031' D. F.	
	Casing Record	Production:	3029' G. R.	
	261' - 8 5/8"	Cement Record		
		200 sacks cement		

Figures Indicate Bottom of Formations

0'	40'	Surface Clay
40'	195'	Sand & Clay
195'	220'	Post Rock
220'	260'	Shale
260'	2245'	Shale
2245'	2563'	Shale & Gyp
2563'	2684'	Redbed & Shale
2684'	2720'	Anhy.
2720'	2905'	Shale & Shells
2905'	3155'	Shale & Lime
3155'	3215'	Shale & Shells
3215'	3249'	Lime & Shale
3249'	3308'	Sand & Shale
3308'	3479'	Lime & Shale
3479'	3580'	Lime & Shale
3580'	4278'	Lime
4278'	T.D.	

RECEIVED
 STATE CORPORATION COMMISSION
 JUN 4 1968 JUN 4 1968
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
)ss
 COUNTY OF ELLIS)

I, Leo F. Dreiling, of the L. J. Dreiling & Sons, Inc., upon oath states that the above and foregoing is a true and correct copy from the Daily Drilling Report from your Flanagin #1.

Leo F. Dreiling

 LEO F. DREILING

Subscribed and sworn to before me this 3rd. day of June 1968.

Joseph A. Hess

 JOSEPH A. HESS NOTARY PUBLIC

My commission expires: September 19, 1970

