


JAN 27 1978
JAN 27 1978
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Thomas County. Sec. 16 Twp. 7S Rge. 32 EX/W
Location as "NE/CNW 1/4 SW 1/4" or footage from lines
SW NE NW 990' FNL - 1650' FWL
Lease Owner Cities Service Company
Lease Name Knudson "A" Well No. 2
Office Address 209 E. William, Wichita, Kansas 67202
Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole



Locate well correctly on above
Section Plot

Date Well completed 12-22 1977
Application for plugging filed 12-6 1977
Application for plugging approved 12-8 1977
Plugging commenced 12-22 1977
Plugging completed 12-22 1977
Reason for abandonment of well or producing formation Not economical to produce

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazar
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4380'

Show depth and thickness of all water, oil and gas formations. 1627

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	361'	None
				4 1/2"	1613'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

- Mud to 1300 ft.
- C.I. Bridge Plug @ 1300 ft.
- C.I. Bridge Plug @ 1136 ft.
- C.I. Bridge Plug @ 1000 ft.
- C.I. Bridge Plug @ 750 ft.

Pump in 1/2 sack hulls, 35 sacks 50/50 Pozmix "A" + 6% gel, filled to surface.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton Oil Well Cementing Co.

STATE OF Kansas COUNTY OF Sedgwick, ss.
E. W. Peterman (employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

STATE NOTARY PUBLIC
Sedgwick County, Kansas

(Signature) E. W. Peterman
209 E. William, Wichita, KS 67202
(Address)

SUBSCRIBED AND SWORN TO before me this _____ day of _____, 19 _____

commission expires 6-3-81

Glenn E. Meier Notary Public.