

15-141-20011-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Osborne County, Sec. 4 Twp. 8S Rge. 14 (W)

Location as "NE/CNW4SW4" or footage from lines C SW NW

Lease Owner Neven H. Veail

Lease Name Snyder Well No. I

Office Address 1401 McKinley, Great Bend, Kansas 67530

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 8-25-68

Application for plugging filed 8-25-68

Application for plugging approved 8-25-68

Plugging commenced 8-25-68

Plugging completed 8-25-68

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey

Producing formation Depth to top Bottom Total Depth of Well Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.


3850 - 450 - Heavy rotary mud
450 - 180 - Plug, 50 sacks cement
450 - 180 - Heavy rotary mud
180 - 180 - Plug, 20 sacks mud
180 - 40 - Heavy rotary mud
40 - GL - Plug, 10 sacks cement, 1/2 sack hulls

Work done by Allied Cement equipment

RECEIVED
STATE CORPORATION COMMISSION
SEP 3 1968
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor Peel Brothers, Inc.
Address Box 359, Hoisington, Kansas 67544

STATE OF Kansas, COUNTY OF Barton, ss.
I, Peel Brothers, Inc. (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.
(Signature) Wendell C. Peel, President



SUBSCRIBED AND SWORN TO before me this 28th day of August, 1968

My commission expires 6-21-70 Ethel S. Williamson Notary Public.

DRILLER'S LOG

Well Owner:	Neven H. Veail	
Farm Name:	Snyder #1	Section 4-8S-14W
Date Started:	8-17-68	Osborne County, Kansas
Date Completed:	8-25-68	
Total Depth:	3850	

Casing: 8-5/8" set at 211' cemented

Contractor: Peel Brothers, Inc.

Figures below are the bottoms of the formations:

Clay	0 - 40
Sand	605
Red Bed	1055
Anhydrite	1096
Shale	1550
Shale and Lime	2640
Lime and Shale	3080
Lime and Sand	3515
Lime	3850
Total Depth	3850


RECEIVED
STATE CORPORATION COMMISSION
SEP 3 1968
CONSERVATION DIVISION
Wichita, Kansas
9-3-68

This is to certify that the above information is true and correct to the best of our knowledge.

PEEL BROTHERS, INC.

Wendell C. Peel

Wendell C. Peel
President



SUBSCRIBED AND SWORN to before me this 28th day of August, 1968.

Ethel S. Williamson
Ethel S. Williamson
Notary Public

My Commission expires 6-21-70