


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

15-141-00038-00-00

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Osborne County. Sec. 19 Twp. 8 Rge. 14 (E) (W)
Location as "NE/CNW/SW" or footage from lines SW SE SE
Lease Owner Trans Era Petroleum, Inc.
Lease Name Hackerott Well No. 1
Office Address Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 4/12/55 19
Application for plugging filed 4/11/55 19
Application for plugging approved 4/11/55 19
Plugging commenced 4/12/55 19
Plugging completed 4/12/55 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Milton Galyardt
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3911 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	221	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugging Record

Filled hole to 220' with heavy mud, 1/2 sacks hulls, wooden plug and 20 sacks cement through drill pipe. Filled with heavy mud, 1/3 sacks hulls and wooden plug and 10 sacks cement. Tied top plug.

RECEIVED
STATE CORPORATION COMMISSION
APR 16 1955
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Trans Era Petroleum, Inc.
Address Box 633, Russell, Kansas 4-16-55

STATE OF KANSAS, COUNTY OF RUSSELL, ss.
H. R. Michaelis (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.
(Signature) H. R. Michaelis

SUBSCRIBED AND SWORN TO before me this 14th day of April, 19 55
Margie Cooper
My commission expires 1-30-57 Notary Public.

PLUGGING
FILE SEC 19 T 8 R 140
BOOK PAGE 11 LINE 11

15-141-00038-00-00

Trans Era Petroleum, Inc.
Hackerott #1

SW SE SE 19-8-14
Osborne County, Ks.

Total Depth: 3911
Comm. 3/29/55
Comp. 4/12/55

Casing

8 5/8" @ 221 feet

Cement

175 sacks of Vickers

FORMATION	DEPTH
Shale	221
Shale-Sand-Shale	1000
Red Bed	1080
Anhydrite	1110
Shale	1550
Shale & Lime	1980
Lime & Shale	2545
Shale & Lime	2635
Lime & Shale	2855
Shale & Lime	3162
Lime	3390
Lime & Shale	3495
Lime & Chert	3570
Lime	3585
Lime, chert & Shale	3652
Lime & Chert	3689
Lime	3741
Lime & Chert	3797
Lime	3866
Simpson	3883
Arbuckle	3911

STATE OF KANSAS)
) ss:
COUNTY OF RUSSELL)

REGISTRY DIVISION
Topeka, Kansas
4-16-55

I hereby certify that the above information is true and correct to the best of my knowledge.

[Signature]

Subscribed and sworn to before me this 14th day of April, 1955

My commission expires 1-30-57.

Margie Cooper
Notary Public

PLUGGING
FILE SEC 19 T 8 R 14 W
BOOK PAGE 111 LINE 11