


15-141-00050-00-00

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Biting Building  
Wichita, Kansas

Osborne County. Sec. 22 Twp. 8 Rge. (E) 14 (W)  
Location as "NE/CNW/SW" or footage from lines NW NW NW  
Lease Owner Cities Service Oil Co.  
Lease Name Bowen Well No. \_\_\_\_\_  
Office Address Bartlesville, Oklahoma  
Character of Well (completed as Oil, Gas or Dry Hole) dry hole  
Date well completed 8/17 19 57  
Application for plugging filed 8/19 19 57  
Application for plugging approved 8/20 19 57  
Plugging commenced 8/18 19 57  
Plugging completed 8/18 19 57  
Reason for abandonment of well or producing formation \_\_\_\_\_

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19 \_\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Milton Galyardt  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4085 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	237'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole to 230' with mud, 1/2 sx hulls and Howco plug at 230', 5' rock on plug. Mixed and dumped 20 sx cement on the rock. Mud to 40' of surface, 1/2 sx hulls and Howco plug, 10 sx cement to surface.

RECEIVED  
SEP 3 1957  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Peel Drlg. Co.  
Address Hoisington, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.  
Roy J. Turner (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God

(Signature) Roy J. Turner  
Box 553, Russell, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of August, 19 57

My commission expires March 17, 1959 W. B. Smith Notary Public.

PLUGGING  
FILE SEC 22 T 8 R 14W  
BOOK PAGE 30 LINE 6

# WELL RECORD

15-141-00050-00-00

WILDCAT.....  
 DISCOVERY.....  
 POOL.....

COMPANY Citizen Service Oil Co. WELL # 1 FARM Down  
 LOCATION 330' S. & 330' E. of NW Cor., Section 22, Township 8, Range 14 W.

ELEV. 1845 (1840 Gr.) CO. Osborne STATE Kansas  
 IP. Dry hole. P. & A. August 17, 1957.

PERFS.....  
 FRAC..... ACID None  
 T.D. 4085' PBTD..... GRAV/GOR.....  
 DRLG. COMM. July 30, 1957 COMP. August 16, 1957 CONTRACTOR Gleam W. Pool

**CASING RECORD:**

2-5/8" at 237' with 175 sz. cement.

**FORMATION RECORD:**

shale and shells	0-237
shale	450
shale & streaks sand	575
red rock and pyrite	620
sand	670
red rock and pyrite	900
red bed and sand	1078
anhydrite	1110
shale	1300
shale and lime	2035
lime and shale	2397
shale and lime	2860
lime and shale	3020
lime	3080
lime and shale	3115
lime	3295
lime and shale	3590
shale and lime	3605
shale and chert	3675
lime, shale and chert	3743
chert	3770
lime, shale and chert	3875
cored lime (rec. 4')	3885
lime	3920
lime and shale	4075
lime	4085 T.D.

Topoka	281A
Heebner	309A
Dodge	307B
Lansing	3102
Base Kansas City	3410
Viola	3857
Simpson	4008
Arbuckle	4049
Pen.	36'
T.D.	4085

- D.S.T. 3053-80, open 1 hour, rec. 45' thin mud; B.H.P. 1200# in 30 minutes.
- D.S.T. 3098-3115, open 30 minutes, rec. 9' mud; B.H.P. 73# in 30 minutes.
- D.S.T. 3125-85, open 30 minutes, rec. 15' mud; B.H.P. 58# in 30 minutes.
- D.S.T. 3447-65, open 30 minutes, rec. 6' mud; B.H.P. 0# in 30 minutes.
- D.S.T. 3477-96, open 30 minutes, rec. 10' mud; B.H.P. 0# in 30 minutes.
- D.S.T. 3520-35, open 30 minutes, rec. 10' mud; B.H.P. 14# in 30 minutes.
- D.S.T. 3540-90, open 30 minutes, rec. 18' mud; B.H.P. 542# in 30 minutes.
- D.S.T. 3671-3740, open 30 minutes, rec. 1520' salt water; B.H.P. 1278# in 30 mins.

SLASH TESTS (SYFO):  
 500' - 1°  
 1000' - 2°  
 2000' - 1°  
 2500' - 0°

**PLUGGING**

FILE SEC 22 T 8 R 14W

BOOK PAGE 38 LINE 6

7-7/8" Rotary hole.