

15-065-~~02954~~⁰²⁹⁵⁴-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING APPLICATION FORM
(File One Copy)

API Number drilled 8-2-58 (of this well) (This must be listed; if no API# was issued, please note drilling completion data.) 6/88

LEASE OPERATOR Cities Service Oil and Gas Corp. OPERATORS LICENSE NO. 5447

ADDRESS 3545 NW 58th Street, Oklahoma City, OK 73112 PHONE # (405) 949-4400
660' FSL

LEASE (FARM) Fabricius Unit WELL NO. 201 WELL LOCATION 1980' FEL COUNTY Graham

SEC. 24 TWP. 7S RGE 23 (W) Total Depth 3705' PLUG BACK TD 3668'

CHECK ONE:

OIL WELL X GAS WELL D & A SWD OR INJ WELL DOCKET NO.

SURFACE CASING SIZE 8-5/8" SET AT 227' CEMENTED WITH 175 SACKS

CASING SIZE 5-1/2" SET AT 3704' CEMENTED WITH 100 SACKS

PERFORATED AT 3645-47' & 3652-56'

CONDITION OF WELL: GOOD X POOR CASING LEAK JUNK IN HOLE

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL KCC field approved plugging procedure is attached.

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? YES

IS ACO-1 FILED? Drilled 1958

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN: Unknown at this time.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

NAME J. D. Hininger PHONE # (913) 674-2182

ADDRESS Cities Service Oil and Gas Corp., P.O. Box 38, Hill City, Kansas 67642

PLUGGING CONTRACTOR Halliburton Oil Services LICENSE NO.

ADDRESS Oberlin, KS 67749 PHONE # (913) 475-2228

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT

SIGNED: Raymond Hininger
(Operator or Agent)

STATE CORPORATION COMMISSION

DATE: 3-16-88

MAR 15 1988

CONSERVATION DIVISION
Wichita, Kansas

3/15/88

4

15-065-~~02971~~⁰²⁹⁵⁴-00-00

CITIES SERVICE OIL AND GAS CORPORATION

INTEROFFICE LETTER

December 11, 1987

TO: Mick D. Harrison
FROM: Phil Pringle
SUBJECT: Plugging Procedure Fabricius U. #201
660' FSL - 1980' FEL
Sec 24-7S-23W
Graham County, Kansas

Well Data:

8-5/8" surface casing at 227' w/ 175 sx
5-1/2" production casing at 3704' w/ 100 sx
Perforations: 3645-47', 3652-56'
PBSD: 3668'

Shallow Formation Data:

Dakota \approx 720-875'
Cheyenne \approx 970-1125'
Anhydrite at 1888-1918'

KCC Field Approval by Mr. Dennis Hamel (11-16-87):

1. Prior to plugging, contact Mr. Hamel at KCC District Office #4, Hays, Kansas; phone number (913) 628-1200.
2. Perforate above the anhydrite at 1878' w/ 4 SPF, perforate below the Dakota at 925' w/3 SPF and perforate below the surface casing at 250' w/ 3 SPF.
3. Tie onto the 5-1/2" and fill the long pipe and casing annulus with cement, hulls & flocele to surface (approximately 250 sx cement, 6 sx hulls & 63# flocele).
4. Let cement sit 48 hours, check TOC & cap well.

NOTE: Cement calculations are based on 65/35 cement w/ 10% gel + 2% econolite additive. Slurry volume 3.62 cu ft/sx, blend ratio 23 gallons water/sx. *ADD 1/4 POUND FLOCELE/SX SLURRY.*

RECEIVED
STATE CORPORATION COMMISSION

MAR 15 1988
3-15-1988
CONSERVATION DIVISION
Wichita, Kansas

State of Kansas



15-065-02954-00-00

Kansas Corporation Commission

MIKE HAYDEN
KEITH R. HENLEY
RICH KOWALEWSKI
MARGALEE WRIGHT
JUDITH McCONNELL
FRANK A. CARO, JR.

GOVERNOR
CHAIRMAN
COMMISSIONER
COMMISSIONER
EXECUTIVE DIRECTOR
GENERAL COUNSEL

CONSERVATION DIVISION
SHARI M. FEIST, DIRECTOR
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, KS 67202-1286
(316) 263-3238

March 16, 1988

WELL PLUGGING NOTICE

NOTICE
MAR 16 '88
EXPIRES

Fabricius Unit #201
660' FSL 1980' FEL
Sec. 24-07S-23W
Graham County

Cities Service Oil & Gas Corporation
3545 NW 58th Street
Oklahoma City, OK 73112


Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

Please contact the district office listed below to review your suggested method of plugging five days prior to plugging the well (KAR-82-3-113).

This notice is void after ninety (90) days from the above date.

Sincerely,



Shari Feist
Director
State Corporation Commission

DISTRICT #4 2301 E. 13th, Hays, KS 67601 (913) 628-1200