

15-065-03323-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 6/4/84

**WELL PLUGGING APPLICATION FORM**  
(File One Copy)

API NUMBER Well Drilled 1958 (of this well) 6/88  
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Cities Service Oil and Gas Corp. OPERATORS LICENSE NO. 5447

ADDRESS 3545 NW 58th Street, Oklahoma City, OK 73112 PHONE # (405) 949-4400

LEASE (FARM) Fabricius U. WELL NO. 106 WELL LOCATION 660' FWL COUNTY GRAHAM

SEC. 25 TWP. 7S RGE. 23 (N) OR (W) TOTAL DEPTH 3700' PLUG BACK TD 3669'

**Check One:**

OIL WELL,  GAS WELL, \_\_\_\_\_ D & A \_\_\_\_\_ SWD or INJ. WELL \_\_\_\_\_ DOCKET NO. \_\_\_\_\_

SURFACE CASING SIZE 8-5/8" SET AT 225' CEMENTED WITH 175 SACKS

CASING SIZE 5-1/2" SET AT 3700' CEMENTED WITH 125 SACKS

PERFORATED AT 3645-47', 3658-65'

CONDITION OF WELL: GOOD  POOR \_\_\_\_\_ CASING LEAK \_\_\_\_\_ JUNK IN HOLE \_\_\_\_\_

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL KCC field approved plugging procedure is attached.

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes

IS ACO-1 FILED? Drilled 1958 (If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN Unknown at this time.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

J.D. Hininger Phone # (913) 674-2182

ADDRESS Cities Service Oil and Gas Corp., P.O. Box 38, Hill City, Kansas 67642

PLUGGING CONTRACTOR Halliburton Oil Services LICENSE NO. \_\_\_\_\_

ADDRESS Oberlin, KS 67749 PHONE # (913) 475-2228

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Raymond [Signature]

(Operator or Agent)

DATE: 3-3-88

STATE CORPORATION COMMISSION

Wichita, Kansas

3/4/88

4



CITIES SERVICE OIL AND GAS CORPORATION

INTEROFFICE LETTER

15-065-03323-00-00

Wichita, Kansas

TO: Mr. M. D. Harrison

FROM: Mr. Phil W. Pringle

SUBJECT: PLUGGING PROCEDURE.....FABRICIUS UNIT 106
LOCATION 660'FWL-660'FWL
SEC 25 TWP 7s RGE 23w
GRAHAM COUNTY, KANSAS

WELL DATA:

SURFACE CSG. 8 5/8" @ 225' w/175 SK
PRODUCTION CSG. 5 1/2" @ 3700' w/125 SK
PERFORATIONS 3645-47; 3658-65'
PBSD 3669' TD
CASING CONDITION GOOD

SHALLOW FORMATION DATA:

DAKOTA 820-940'
CHEYENNE 975-1165'
ANHYDRITE 1890-1930'

KCC FIELD APPROVAL BY MR. DENNIS HAMEL (11/16/87)

- 1) Prior to plugging, contact Mr. Hamel at the District office #4, Hays, Kansas, phone number (913) 628-1200.
2) Perforate above the Anhydrite at 1880' with 4 SPF, perforate below the Dakota at 990' with 3 SPF, and perforate below the surface casing at 230' with 3 SPF.
3) Tie onto the 5-1/2" casing and fill the long pipe & casing annulus to surface with cement, Hulls and Flocele. (Approx. 300 sx cement, 6 sx Hulls and 75 # Flocele.
4) Let cement sit 48 hours, check top of cement and cap well. Note: cement calculations based on 65/35 cement with 10% gel + 2% econolite additive. Slurry volume 3.62 Ft^3/sx, blend ratio 23 gals. water/sx. Add 1/4# Flocele/sx slurry.

cc: J. D. Hininger (2)
Andrew McCalmont
Allen D. Grubb
File

STATE OF KANSAS

1988 APR 4 1008

3/4/88

Wichita, Kansas

State of Kansas



15-065-03323-00-00

Kansas Corporation Commission

MIKE HAYDEN  
KEITH R. HENLEY  
RICH KOWALEWSKI  
MARGALEE WRIGHT  
JUDITH McCONNELL  
FRANK A. CARO, JR.

GOVERNOR  
CHAIRMAN  
COMMISSIONER  
COMMISSIONER  
EXECUTIVE DIRECTOR  
GENERAL COUNSEL

CONSERVATION DIVISION  
SHARI M. FEIST, DIRECTOR  
200 Colorado Derby Bldg.  
202 W. 1st Street  
Wichita, KS 67202-1286  
(316) 263-3238

THIS NOTICE

March 7, 1988

JUN 7 '88

WELL PLUGGING NOTICE

EXPIRES

Fabricius U #106  
4620'FSL 4620'FEL  
Sec. 25-07S-23W  
Graham County

Cities Service Oil & Gas Corporation  
3545 NW 58th Street  
Oklahoma City, OK 73112


Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

Please contact the district office listed below to review your suggested method of plugging five days prior to plugging the well (KAR-82-3-113).

This notice is void after ninety (90) days from the above date.

Sincerely,

  
\_\_\_\_\_  
Shari Feist  
Director  
State Corporation Commission

DISTRICT #4 2301 E. 13th, Hays, KS 67601 (913) 628-1200