

15-065-19076-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER Well Drilled 1964 (of this well) 6/88
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Cities Service Oil and Gas Corp. OPERATORS LICENSE NO. 5447

ADDRESS 3545 NW 58th Street, Oklahoma City, OK 73112 PHONE # (405) 949-4400

LEASE (FARM) Fabricius U. WELL NO. 109S WELL LOCATION 2450' FWL COUNTY GRAHAM

SEC. 25 TWP. 7S RGE. 23 (S) OR (W) TOTAL DEPTH 1915' PLUG BACK TD _____

Check One: * **WATER SUPPLY WELL - CASING CEMENTED TO SURFACE.**

OIL WELL, _____ GAS WELL, _____ D & A _____ SWD or INJ. WELL, _____ DOCKET NO. _____

SURFACE CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

CASING SIZE 7" SET AT 1914' CEMENTED WITH 450 SACKS

PERFORATED AT 1435-85'

CONDITION OF WELL: GOOD X POOR _____ CASING LEAK _____ JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL KCC field approved plugging procedure is attached.

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? _____

IS ACO-1 FILED? Drilled 1964 (If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN Unknown at this time.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

J.D. Hininger Phone # (913) 674-2182

ADDRESS Cities Service Oil and Gas Corp., P.O. Box 38, Hill City, Kansas 67642

PLUGGING CONTRACTOR Halliburton Oil Services LICENSE NO. _____

ADDRESS Oberlin, KS 67749 PHONE # (913) 475-2228

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Raymond Hill
(Operator or Agent)

DATE: 3-3-88

3/4/88

3/4/88

4



15-0025-19076-00-00

CITIES SERVICE OIL AND GAS CORPORATION

INTEROFFICE LETTER

Wichita, Kansas

TO: Mr. M. D. Harrison

FROM: Mr. P. W. Pringle

SUBJECT: PLUGGING PROCEDURE.....FABRICIUS UNIT #109S
 380' FNL-2450' FWL
 SECTION 25-T7S-R23W
 GRAHAM COUNTY, KANSAS

WELL DATA:

7" CASING AT 1914' W/450 SX (CEMENT CIRCULATED)
 PERFORATIONS: 1435-85'
 TOTAL DEPTH: 1915'

SHALLOW FORMATIONS:

DAKOTA ≈ 720'-875'
 CHEYENNE ≈ 970'-1125'
 ANHYDRITE ≈ 1849-81'

KCC FIELD APPROVED BY MR. DENNIS HAMEL

1. Prior to plugging, contact Mr. Hamel at the district office #4, Hays, Kansas, phone No. (913) 628-1200.
2. Connect to the 7" casing, and pump cement and hulls to surface. (Approx. 175 sx cement).
3. Let cement sit 48 hrs., check top of cement, and cap well.

Note: Cement calculations based on 65/35 cement with 10% gel + 2% econolite additive. Slurry volume 3.62 ft.³/sx. Blend ratio 23 gals water/sx.

PWP/mlf

cc: J. D. Hininger
 A. J. McCalmont
 A. D. Grubb
 Well File

STATE CORPORATION COMMISSION
 WICHITA, KANSAS
 APR 4 1988
 3/4/88



15-065-19076-00-00

Kansas Corporation Commission

MIKE HAYDEN
KEITH R. HENLEY
RICH KOWALEWSKI
MARGALEE WRIGHT
JUDITH McCONNELL
FRANK A. CARO, JR.

GOVERNOR
CHAIRMAN
COMMISSIONER
COMMISSIONER
EXECUTIVE DIRECTOR
GENERAL COUNSEL

CONSERVATION DIVISION
SHARI M. FEIST, DIRECTOR
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, KS 67202-1286
(316) 263-3238

THIS NOTICE
MAY 7 '88
EXPIRES

March 7, 1988

WELL PLUGGING NOTICE

Fabricius U #109S
4900'FSL 2830'FEL
Sec. 25-07S-23W
Graham County

Cities Service Oil & Gas Corporation
3545 NW 58th Street
Oklahoma City, OK 73112

Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

Please contact the district office listed below to review your suggested method of plugging five days prior to plugging the well (KAR-82-3-113).

This notice is void after ninety (90) days from the above date.

Sincerely,

Shari Feist

Shari Feist
Director
State Corporation Commission

DISTRICT #4 2301 E. 13th, Hays, KS 67601 (913) 628-1200