

15-065-02956-00-00 1

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING APPLICATION FORM
(File One Copy)

API Number drilled 1958 (of this well) (This must be listed; if no API# was issued, please note drilling completion data.) 6/88

LEASE OPERATOR Cities Service Oil and Gas Corp. OPERATORS LICENSE NO. 5447

ADDRESS 3545 NW 58th Street, Oklahoma City, OK 73112 PHONE # (405) 949-4400
660' FNL

LEASE (FARM) Fabricius Unit WELL NO. 102 WELL LOCATION 1980' FEL COUNTY Graham

SEC. 25 TWP. 7S RGE 23 (W) Total Depth 3675' PLUG BACK TD 3640'

CHECK ONE:

OIL WELL X GAS WELL _____ D & A _____ SWD OR INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8-5/8" SET AT 220' CEMENTED WITH 175 SACKS

CASING SIZE 5-1/2" SET AT 3675' CEMENTED WITH 125 SACKS

PERFORATED AT 3617-28'

CONDITION OF WELL: GOOD X POOR _____ CASING LEAK _____ JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL KCC field approved plugging procedure is attached.

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? YES

IS ACO-1 FILED? Drilled 1958

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN: Unknown at this time.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

NAME J. D. Hininger PHONE # (913) 674-2182
ADDRESS Cities Service Oil and Gas Corp., P.O. Box 38, Hill City, Kansas 67642

PLUGGING CONTRACTOR Halliburton Oil Services LICENSE NO. _____
ADDRESS Oberlin, KS 67749 PHONE # (913) 475-2228

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Raymond Hill
(Operator or Agent)

RECEIVED
STATE CORPORATION COMMISSION

DATE: 3-14-88

MAR 15 1988
3/15/88
CONSERVATION DIVISION
Wichita, Kansas



15-065-02956-00-00

CITIES SERVICE OIL AND GAS CORPORATION

INTEROFFICE LETTER

December 11, 1987

TO: Mick D. Harrison
FROM: Phil Pringle
SUBJECT: Plugging Procedure Fabricius U. #102
660' FNL - 1980' FEL
Sec 25-7S-23W
Graham County, Kansas

Well Data:

8-5/8" surface casing at 220' w/ 175 sx
5-1/2" production casing at 3675' w/ 125 sx
Perforations: 3617-28'
PBSD: 3640'

Shallow Formation Data:

Dakota \approx 720-875'
Cheyenne \approx 970-1125'
Anhydrite 1849-82'

KCC Field Approval: Mr. Dennis Hamel (11-16-87)

1. Prior to plugging, contact Mr. Hamel at the District Office #4, Hays, Kansas; phone number (913) 628-1200.
2. MIRU - Pull rods, BHP & tubing.
3. Perforate above the anhydrite at 1839' w/ 4 SPF, perforate below the Dakota at 925' w/ 3 SPF and below surface casing at 250' w/ 3 SPF.
4. Tie onto the 5-1/2" casing and fill the long pipe and casing annulus with cement & hulls to surface (approximately 250 sx cement, 6 sx hulls & 63# flocele).
5. Let cement sit 48 hours, check TOC & cap well.

NOTE: Cement calculations based on 65/35 cement with 10% gel + 2% econolite additive. Slurry volume 3.62 cu ft/sx, blend ratio 23 gallons water/sx. Add 1/4 pound flocele/cu ft.

RECEIVED
CORPORATION COMMISSION
MAR 15 1988
3-15-1988
CONSERVATION DIVISION
Wichita, Kansas



15-065-02956-00-00

Kansas Corporation Commission

MIKE HAYDEN GOVERNOR
KEITH R. HENLEY CHAIRMAN
RICH KOWALEWSKI COMMISSIONER
MARGALEE WRIGHT COMMISSIONER
JUDITH MCCONNELL EXECUTIVE DIRECTOR
FRANK A. CARO, JR. GENERAL COUNSEL

CONSERVATION DIVISION
SHARI M. FEIST, DIRECTOR
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, KS 67202-1286
(316) 263-3238

THIS NOTICE
EXPIRES
JUN 13 '88

March 16, 1988

WELL PLUGGING NOTICE

Fabricius Unit #102
660'FNL 1980'FEL
Sec. 25-07S-23W
Graham County

Cities Service Oil & Gas Corporation
3545 NW 58th Street
Oklahoma City, OK 73112

Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

Please contact the district office listed below to review your suggested method of plugging five days prior to plugging the well (KAR-82-3-113).

This notice is void after ninety (90) days from the above date.

Sincerely,

Shari Feist

Shari Feist
Director
State Corporation Commission

DISTRICT #4 2301 E. 13th, Hays, KS 67601 (913) 628-1200