

15-065-02957-00-05

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER Well Drilled 1958 (of this well) 6/88
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Cities Service Oil and Gas Corp. OPERATORS LICENSE NO. 5447

ADDRESS 3545 NW 58th Street, Oklahoma City, OK 73112 PHONE # (405) 949-4400

LEASE (FARM) Fabricius U. WELL NO. 103 WELL LOCATION 1980' FNL 3300' FSL 3300' FEL
~~1980' FNL~~ COUNTY GRAHAM

SEC. 25 TWP. 7S RGE. 23 OR (W) TOTAL DEPTH 3650' PLUG BACK TD 3628'

Check One:

OIL WELL GAS WELL D & A SWD or INJ. WELL DOCKET NO. _____

SURFACE CASING SIZE 8-5/8" SET AT 223' CEMENTED WITH 150 SACKS

CASING SIZE 5-1/2" SET AT 3650' CEMENTED WITH 125 SACKS

PERFORATED AT 3599'-3609'

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL KCC field approved plugging procedure is attached.

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes

IS ACO-1 FILED? Drilled 1958 (If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN Unknown at this time.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

J.D. Hininger Phone # (913) 674-2182

ADDRESS Cities Service Oil and Gas Corp., P.O. Box 38, Hill City, Kansas 67642

PLUGGING CONTRACTOR Halliburton Oil Services LICENSE NO. _____

ADDRESS Oberlin, KS 67749 PHONE # (913) 475-2228

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Raymond Hill

DATE: 3-3-88

3/4/88



CITIES SERVICE OIL AND GAS CORPORATION

INTEROFFICE LETTER

15-065-02957-00-00

Wichita, Kansas

TO: Mr. M. D. Harrison

FROM: Mr. Phil W. Pringle

SUBJECT: PLUGGING PROCEDURE.....FABRICIUS UNIT 103
 LOCATION 1980' FNL-1980' FWL
 SEC 25 TWP 7s RGE 23W
 GRAHAM COUNTY, KANSAS

WELL DATA:

SURFACE CSG. 8 7/8" @ 223' w/150 SX
 PRODUCTION CSG. 5 1/2" @ 3650' w/125 SX
 PERFORATIONS 3599-3609'
 PBTD 3628' TD _____
 CASING CONDITION GOOD

SHALLOW FORMATION DATA:

DAKOTA 705-850'
 CHEYENNE 925-1090'
 ANHYDRITE 1825-60'

KCC FIELD APPROVAL BY MR. DENNIS HAMEL (11/16/87)

- 1) Prior to plugging , contact Mr. Hamel at the District office #4, Hays, Kansas, phone number (913) 628-1200.
- 2) Perforate above the Anhydrite at 1815' with 4 SPF, perforate below the Dakota at 900' with 3 SPF, and perforate below the surface casing at 228' with 3 SPF.
- 3) Tie onto the 5-1/2" casing and fill the long pipe & casing annulus to surface with cement, Hulls and Flocele.
(Approx. 300 sx cement, 6 sx Hulls and 75 # Flocele.
- 4) Let cement sit 48 hours, check top of cement and cap well.
Note: cement calculations based on 65/35 cement with 10% gel + 2% econolite additive. Slurry volume 3.62 Ft³/sx, blend ratio 23 gals. water/sx. Add 1/4# Flocele/sx slurry.

cc: J. D. Hininger (2)
 Andrew McCalmont
 Allen D. Grubb
 File

STATE OF KANSAS

APR 11 1988

COMM. REG. DIV.

3/4/88



15-065-02957-00-00

Kansas Corporation Commission

MIKE HAYDEN
KEITH R. HENLEY
RICH KOWALEWSKI
MARGALEE WRIGHT
JUDITH McCONNELL
FRANK A. CARO, JR.

GOVERNOR
CHAIRMAN
COMMISSIONER
COMMISSIONER
EXECUTIVE DIRECTOR
GENERAL COUNSEL

CONSERVATION DIVISION
SHARI M. FEIST, DIRECTOR
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, KS 67202-1266
(316) 263-3238

THIS NOTICE

March 7, 1988

will 7 '88

WELL PLUGGING NOTICE

EXPIRES

Fabricius U #103
3300' FSL 3300' FEL
Sec. 25-07S-23W
Graham County

Cities Service Oil & Gas Corporation
3545 NW 58th Street
Oklahoma City, OK 73112

Gentlemen;

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

Please contact the district office listed below to review your suggested method of plugging five days prior to plugging the well (KAR-82-3-113).

This notice is void after ninety (90) days from the above date.

Sincerely,

Shari Feist

Shari Feist
Director
State Corporation Commission

DISTRICT #4 2301 E. 13th, Hays, KS 67601 (913) 628-1200