

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

15-141-20022-0000

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 1973 (of this well)
(This must be listed; if no API# was issued, please note drilling completion date.) 6/88

LEASE OPERATOR Petroleum Management, Inc. OPERATORS LICENSE NO. 5242

ADDRESS 400 N. Woodlawn, Suite 201, Wichita, KS 67208 PHONE # (316) 686-7287

LEASE (FARM) Spears WELL NO. 2 WELL LOCATION SW SE SE COUNTY Osborne

SEC. 15 TWP. 8S RGE. 14 ~~EX~~ (W) TOTAL DEPTH 2635' PLUG BACK TD 2580'

Check One:

OIL WELL GAS WELL _____ D & A _____ SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8-5/8" SET AT 200' CEMENTED WITH 150 SACKS

CASING SIZE 5-1/2" SET AT 2593' CEMENTED WITH 50 SACKS

PERFORATED AT 2570' to 2576'

CONDITION OF WELL: GOOD POOR _____ CASING LEAK _____ JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Cement above perfs, pull ±1200' of pipe,
mud to base anhydrite, cement at anhydrite, mud to 50', cement at surface.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? yes IS ACO-1 FILED? no
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 0900 May 18, 1988

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Don Keener PHONE # (913) 434-2042

ADDRESS Box H, Plainville, KS 67663

PLUGGING CONTRACTOR Petroleum Management, Inc. LICENSE NO. _____

ADDRESS 400 N. Woodlawn, Suite 201, Wichita, KS 67208 PHONE # (316) 686-7287

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Steven P. O'Neill

(Operator or Agent)

Steven P. O'Neill

DATE: May 17, 1988

RECEIVED
STATE CORPORATION COMMISSION
MAY 18 1988
5-18-88
CONSERVATION DIVISION
Wichita, Kansas
5242



State of Kansas



15-141-20022-00-00

Kansas Corporation Commission

MIKE HAYDEN GOVERNOR
KEITH R. HENLEY CHAIRMAN
RICH KOWALEWSKI COMMISSIONER
MARGALEE WRIGHT COMMISSIONER
JUDITH McCONNELL EXECUTIVE DIRECTOR
FRANK A. CARO, JR. GENERAL COUNSEL

CONSERVATION DIVISION
SHARI M. FEIST, DIRECTOR
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, KS 67202-1286
(316) 263-3238

May 18, 1988

THIS NOTICE

AUG 18 '88

EXPIRES

WELL PLUGGING NOTICE

Spears #2
SW SE SE
Sec. 15-08S-14W
Osborne County

Petroleum Management, Inc.
400 N. Woodlawn, Ste. 201
Wichita, KS 67208


Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

Please contact the district office listed below to review your suggested method of plugging five days prior to plugging the well (KAR-82-3-113).

This notice is void after ninety (90) days from the above date.

Sincerely,



Shari Feist
Director
State Corporation Commission

DISTRICT #4 2301 E. 13th, Hays, KS 67601 (913) 628-1200

15-141-20022-00-00

DRILLERS LOG

No. 2 Spears

CASING RECORD:

8-5/8" @ 200'
w/150 sx cement

5-1/2" @ 2593'
w/50 sx cement

TOTAL DEPTH: 2580'

COMPANY: Petroleum Management, Inc.

CONTRACTOR: Red Tiger Drilling Co.

COMMENCED: August 10, 1973

COMPLETED: August 14, 1973

DESCRIPTION:

Apx. SW SE SE
15-8S-14W
Osborne County,
Kansas

ELEVATION:

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Shale & Shells	0	220	
Shale	220	1116	
Anhydrite	1116	1149	
Shale	1149	1535	
Shale & Lime	1535	2395	
Lime	2395	2580	

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Linda H. Dickens
Linda H. Dickens

Subscribed and sworn to before me this 17th day of August, 1973.

Linda C. Mowrey
Notary Public

My Commission Expires:

May 24, 1977



RECEIVED
STATE CORPORATION COMMISSION
5-10-88
MAY 10 1988

CONSERVATION DIVISION
Wichita, Kansas