

State of Kansas



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION

MAR 2 1982
MAR 2 - 1982
CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

Dear Sir:

Mr. Millard Kelso of Kelso Casing has this date requested permission to plug the following described well:

Operator's Full Name: Amercrombie - Inc.

Complete Address: 801 Union Ctr - Wichita, Kansas 67202

Lease Name: Ray Well No. 1

Location: SW-SE-SE Sec. 36 Twp. 7 Rge. 24 (E) (W)

County: Graham Total Depth: 3850'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Kelso was instructed to plug the well as follows:

8 5/8" set @ 165' w/175 sk comman -> 4 1/2" set @ 3849' w/150 sk
Top perf @ 3669 - Plug back @ 3600' - sand 50' + 4 sk emt.
3 shots rec. 1819' casing - Ordered 140 sk 50% poz mix 4% gel 3% cc
20 S.gel - 5 hulls + 8 5/8" plug - Pumped in 4 hulls -> 12 gel ->
70 emt -> 1 hull -> 8 gel -> 70 emt. (emt by allied)

Very truly yours,

Dennis L. Hamel
Conservation Division Agent