



15-065-20163-00-00

ROBERT B. DOCKING Governor
DALE E. SAFFELS Chairman
JULES V. DOTY Commissioner
JAMES O. GREENLEAF Commissioner
RAYMOND B. HARVEY Secretary
JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Lyle Hicks of L. J. Dreiling & Sons, Inc., has this date requested permission to plug the following described well:

Mr. Hicks guarantees payment of the plugging fee.

Operator's full Name: Leo J. Dreiling Oil Company

Complete Address: Victoria, Kansas

Lease Name: Hale Well No. 1

Location: CNW-NE Sec. 10 Twp. 7 Rge. (E)(W) 23

County: Graham Total Depth 3887 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Hicks was instructed to plug the well as follows:

174'--8 5/8" Surface pipe, cement circulated with 150 Sx.
Top of Dakota section @ 985'.

Circulate hole with heavy mud. Pull DP to 1210' and displace 100 Sx.
cement thru DP. Pull DP to 210' and displace 20 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

RECEIVED
STATE CORPORATION COMMISSION
AUG 14 1968
CONSERVATION DIVISION
Wichita, Kansas

Very truly yours,
H. L. Nichols
Conservation Division Agent

8-14-68