

State of Kansas



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 23 1967  
JAN 23 1967

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Dale Bucheister of John O. Farmer, Inc., has this date requested permission to plug the following described well:

Mr. Bucheister guarantees payment of the plugging fee.

Operator's full Name: John O. Farmer, Incorporated,

Complete Address: 370 W. Wichita, Russell, Kansas.

Lease Name: Heskett Well No. 1

Location: NE-NE-SW Sec. 32 Twp. 7 Rge. (E)(W) 25

County Graham Total Depth 3967 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Bucheister was instructed to plug the well as follows:

207'--8 5/8" Surface pipe, cement circulated with 135 Sx.

Circulate hole with heavy mud, set plug @ 600' and 20 Sx. cement.

"		210' with $\frac{1}{4}$ sk. hulls & 20 Sx. cement.
"		40' with $\frac{1}{2}$ sk. hulls & 10 Sx. cement.

Very truly yours,

W. L. Nichols  
Conservation Division Agent