

State of Kansas



15-065-20081-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Roy Cook of Imperial Oil Company, has this date requested permission to plug the following described well:

Mr. Cook guarantees payment of the plugging fee.

Operator's full Name: Imperial Oil Company,

Complete Address: 780 4th National Bank, Bldg., Wichita, Kansas.

Lease Name: Dawes Well No. 1

Location: CSE-NE Sec. 30 Twp. 7 Rge. (E)(W) 25

County Graham Total Depth 3942 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Cook was instructed to plug the well as follows:

207'--8 5/8" Surface pipe, cement circulated with 165 Sx.  
Dakota section from 1785' to 1945'.

Circulate hole with heavy mud. Pull DP to 2000' and displace 100 Sx.  
cement thru DP. Pull DP to 210' and displace 20 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

RECEIVED  
STATE CORPORATION COMMISSION

SEP 12 1967  
SEP 12, 1967  
CONSERVATION DIVISION  
Wichita, Kansas

Very truly yours,

M. L. Nichols  
Conservation Division Agent