

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-01029-00-01
Spot: NWSE Sec/Twnshp/Rge: 18-11S-24W
1980 feet from S Section Line, 1980 feet from E Section Line
Lease Name: SCANLON Well #: 3
County: TREGO Total Vertical Depth: 3950 feet

Operator License No.: 31866
Op Name: RL INVESTMENT, LLC
Address: 217 SAINT PETER ST.
MORLAND, KS 67650

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3942	0	w/75 sxs cmt
SURF	8.625	168	0	w/110 sxs cmt

\$128³⁸

Well Type: EOR UIC Docket No: E27424.1 Date/Time to Plug: 01/19/2006 2:45 PM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: RANDALL PFEIFER Company: RL INVESTMENT, LLC Phone: (785) 627-5711

Proposed Plugging Method: Ordered 75 sxs cement.

Plugging Proposal Received By: ROGER MOSES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/19/2006 3:45 PM KCC Agent: ROGER MOSES

Actual Plugging Report:

Perfed and squeezed at 1100' w/175 sxs cement.
Squeezed at 1450' to 1890' w/275 sxs cement.
2 3/8" tubing cemented bottom (3885') to surface with 126 sxs.
Tied to 2 3/8' tubing and squeezed 75 sxs 60/40 pozmix - 10% gel.
Max. P.S.I. 1000#. S.I.P. 1000#.

Perfs:

Top	Bot	Thru	Comments
3942	3950		
3920	3924		
3900	3905		

RECEIVED
FEB 01 2006
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY. PFEIFER DOZER-WATER.

Plugged through: TBG

District: 04

Signed Roger L. Moses
(TECHNICIAN)

INVOICED
DATE 2.2-06
INV. NO. 2006061054

Form CP-2/3

JAN 25 2006

replacement card

RL INVESTMENT
MORLAND KS 67650

18-11S-24W
C NW SE

3 SCANLON OWWO

site: 3-1/4 N & 4-1/2 E OF COLLYER KS

dy: TREGO

API 15-195-01029

contr: LUDWICK WELL SVC

field: SCANLON

rod: NONE

fr date 02/14/97

spd date 03/25/97

drig comp 03/31/97

card issued 03/30/98

last revised 08/10/98

ELV: 2418 KB, 2413 GL LOG
tops.....depth/datum

* ANH2020 + 398
 HEEB3724 -1306
 TOR3743 -1325
 LANS3756 -1338
 LTD OLD3950 -1532
 RTD OLD3950 -1532
 * SAMPLE TOP

IP status:

INJ, LKC 3898-3950 OA, 12/17/97
 INFO RELEASED: 8/10/98 - WAS INJ - TEMP COMP
 OLD INFO: OPERATOR WAS JOHN O FARMER, 3
 SCANLON, SPD 11/21/63, 12/01/63 8-5/8" 160 / 110 SX,
 4-1/2" 3942 / 75 SX, OIL, P 50 BOPD, NW, LKC 3942-3950,
 01/15/64 (CARD ISSUED 01/23/64)
 CONTR: JOHN O FARMER
 COMMENT: WAS API IOG-32128
 NO CORES
 DST (1) 3910-3927 (LKC), / 60-20, REC 30' M, W / SLI SO
 ISIP 86# FSIP 47# IFP 23# FFP 39#

COPYRIGHT 1998
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

(over)

RL INVESTMENT
MORLAND KS 67650

18-11S-24W
C NW SE

3 SCANLON OWWO

DST (2) 3895-3950 (LKC), / 60-20, REC 15' M, 60' HOCM, 550' FROGGY OIL, 915' GSY OIL
ISIP 1364# FSIP 1276# IFP 62# FFP 542#

MICT - CO, (LKC OH), FU 350' OIL & M / 12 HRS, FU 2900' FL / 12 HRS, SWB 7 BBL VHO (2%
WTR), FU 2900' OIL / 12 HRS, POP, P 50 BOPD, NW, 1/15/64

NEW INFO: FR 02/14/97, RE-ENTERED 03/25/97 WSH DWN DC 03/31/97 CSG: PROD CSG
ALREADY IN HOLE

COMMENT: KCC API 15-195-01029-0000; ELEV ON REWORK IS 2416 GL

TRGT ZN: LKC, PTD 3950 (LKC), MICT - CO, PF FOR SQZ 1513-1797, SQZ'D W/150 SX, PF FOR
SQZ 1451-1555, SQZ'D W/100 SX, DO CMT, CO TO 3950, (LKC OH) & PF (LKC) 3898-3904, 3920-
3924, SET 2-3/8" TBG AT 3875 / 125 SX, CONVERTED TO WIW - INJECTION RATE
SATISFACTORY, 12/17/97