

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-22768-00-00  
Spot: N2NW Sec/Twnshp/Rge: 33-19S-11W  
4620 feet from S Section Line, 3960 feet from E Section Line  
Lease Name: PFAFF Well #: 1  
County: BARTON Total Vertical Depth: 3408 feet

Operator License No.: 7383  
Op Name: BOLDING, GRADY CORPORATION  
Address: PO BOX 486  
ELLINWOOD, KS 67526

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3415	0	125 SX CMT
SURF	8.625	275	0	225 SX CMT

#110 76

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/31/2006 1:30 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: Ordered 225 sxs 60/40 pozmix - 10% gel - 500# hulls.  
Fluid level 200'.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 01/31/2006 5:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Sanded off bottom to 3200' and topped with 5 sxs cement using a dump bailer.  
Cut 5 1/2" casing at 2213'. Pulled one joint casing - got stuck in the hole.  
Re-cut casing at 1936' and again at 1604'.  
Pulled to 1320' - pumped 90 sxs 60/40 pozmix with 200# hulls mixed in.  
Pulled casing to 565' - pumped 40 sxs 60/40 pozmix with 200# hulls mixed in..  
Pulled casing to 370' - pumped 70 sxs cement with 100# hulls mixed in to circulate cement into pit.  
POOH. Hole standing full of cement after pulling rest of the casing.

Perfs:

Top	Bot	Thru	Comments
3362	3364		
3340	3343		

RECEIVED  
FEB 03 2006  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #22554.

Plugged through: CSG

District: 04

Signed

*[Signature]*

(TECHNICIAN)

INVOICED

DATE

2.3.06

REL. NO.

2006061059

Form CP-2/3

FEB 01 2006

ISERN-SCHULTZ OIL & GAS, INC. #1 PFAFF 33-19-11W  
 BOX 486 ELLINWOOD, KS 67526 C N/2 NW  
 CONTR BIG KAT, INC. CTY BARTON  
 GEOL TODD MORGENSTERN FIELD ELLINWOOD NORTH

E 1782 KB CM 4/29/82 CARD ISSUED 7/29/82 IP P 24 BOPD & 75% WTR  
 1777 GL  
 API 15-009-22,768 ARB 3340-3343

+	+	+
+	+	+
+	+	+

LOG	TOPS	DEPTH	DATUM
ANH		540	+1242
HEEB		2912	-1130
TOR		2930	-1148
DOUG		2946	-1164
BR LM		3034	-1252
LANS		3052	-1270
ARB		3314	-1532
PBTD		3379	-1597
LTD		3386	-1604
RTD		3408	-1626

8 5/8" 275/225sx; 5 1/2" 3407/125sx  
 DST (1) 3043-3088(BR LM, LANS)/45-45-45-45, REC 340' GSY CM & O SPKD W, 434' GSY C SW & O SPKS, SIP 964-952#, FP 132-204/336-384#  
 DST (2) 3105-3149(LANS)/30-30-60-60, REC 2066' SW W/F SPKS O, SIP 1000-1023#, FP 240-575/752-905#  
 DST (3) 3302-3322(LANS, ARB)/30-30-30-30, REC 275' M, SIP 168-168#, FP 180-120/144-132#

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS

(OVER)

ISERN-SCHULTZ OIL & GAS, INC. #1 PFAFF 33-19-11W  
 C N/2 NW

DST (4) 3320-3329(ARB)/30-30-30-30, REC 126' GSY M W/FEW O SPKS, SIP 1000-1000#, FP 198-173/206-182#  
 MICT - CO, PF(ARB) 3362-64 w/4 SPF, AC 250G (MA), SWB LD, NON-COMMERCIAL, PF (ARB) 3340-43 w/4 SPF, AC 1000G (MA) & 250G (INS), SWB LD W/GSO, RE-AC 250G (INS), POP, P 24 BOPD & 75% W (GR 41), 6/25/82

WICHITA