

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-22844-00-00
Spot: N2NWNW Sec/Twnshp/Rge: 33-19S-11W
4950 feet from S Section Line, 4620 feet from E Section Line
Lease Name: PFAFF Well #: 2
County: BARTON Total Vertical Depth: 3410 feet

Operator License No.: 7383
Op Name: BOLDING, GRADY CORPORATION
Address: PO BOX 486
ELLINWOOD, KS 67526

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3415	0	125 SX CMT
SURF	8.625	275	0	225 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/02/2006 2:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: Ordered 225 sxs 60/40 pozmix - 10% gel - 500# hulls.
Fluids - well was flowing.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/02/2006 3:45 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Kelso sanded off bottom to 3200' and topped with 5 sxs cement.
Kelso cut casing at 2035'.
Pulled to 1320' - Allied rigged to casing and pumped 90 sxs 60/40 pozmix with 200# hulls mixed in.
Pulled casing to 570' - pumped 40 sxs cement with 200# hulls mixed in.
Pulled casing to 370' - pumped 65 sxs cement with 100# hulls mixed in to circulate cement to surface.
POOH. Pulled rest of casing. Hole standing full.

Perfs:

Top	Bot	Thru	Comments
3378	3380		
3365	3367		
3350	3354		
3334	3338		
3316	3320		

RECEIVED
FEB 06 2006
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #24115.

Plugged through: CSG

District: 04

Signed _____

INVOICED (TECHNICIAN)

DATE 2-7-06

TEL. NO. 2006061067

Form CP-2/3

FEB 03 2006

