

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-21382-00-01
Spot: N2NWSE Sec/Twnshp/Rge: 5-11S-22W
2310 feet from S Section Line, 1980 feet from E Section Line
Lease Name: STITES G Well #: 1
County: TREGO Total Vertical Depth: 3970 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: BOX 783188 8100 E 22ND ST. N. #700
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3970	0	175 SX CMT
SURF	8.625	198	0	135 SX CMT

#129⁰³

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/23/2006 10:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: PETER FIORINI Company: RITCHIE EXPLORATION, INC. Phone: (785) 623-1506

Proposed Plugging Method: Ordered 250 sxs cement and 500# hulls.

Plugging Proposal Received By: BRUCE BASYE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/23/2006 1:00 PM KCC Agent: ROGER MOSES

Actual Plugging Report:

DV at 1728' w/450 sxs - circulate to surface.
Tied to annulus - pressured to 600# P.S.I. - took no cement.
Tied to 4 1/2" casing - squeezed 220 sxs cement with 500# hulls.
Max. P.S.I. 1000#. S.I.P. 800#.
Total of 220 sxs 60/40 pozmix - 10% gel and 500# hulls.

Perfs:

Top	Bot	Thru	Comments
3730	3734		
3723	3726		
3693	3695		
3602	3604		
3396	3398		

RECEIVED
FEB 01 2006
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY. RUSH TANK-WATER.

Plugged through: CSG

District: 04

Signed Roger Moses
(TECHNICIAN)

INVOICED

DATE 2-2-06
INV. NO 2006061053

Form CP-2/3

JAN 27 2006


A. SCOTT RITCHIE
125 N. MARKET, #950
WICHITA, KS 67202

#1 G. STITES

5-11-22W
C N/2 NW SE

CONTR MURFIN DRILLING COMPANY CTY TREGO

GEOL _____ FIELD MCCALL NE EXT (1/8S)



ELV 2256 KB SPD 12/2/83 CARD ISSUED 11/1/84 IP P 30 BO & 50 BWPD
2251 GL LKC 3602-3734 OA
API 15-195-21,382

LOG	Tops	Depth	Datum
ANH	1725 +	531
B/ ANH	1770 +	486
TOP	3270	-1014
HEEB	3490	-1234
TOR	3513	-1257
LANS	3528	-1272
BKC	3760	-1504
MARM	3841	-1585
LTD&RTD	3973	-1717

8 5/8 " 198/135SX, 4 1/2 " 3965/625SX
DST (1) 3391-3450 (MID TOP) / 30-45-30-45, REC 1188' OIL
SPTD M, (35' OIL, 117' M, 1036' W), SIP 1228-1218#, FP 164-
461 / 504-623#
DST (2) 3450-96 (L TOP) / 30-30-30-30, REC 80' MW, NSO, SIP
1228-1164#, FP 67-77 / 88-99#
DST (3) 3551-92 (LKC 35 & 50' ZNS) / 30-45-60-45, REC 180'
OIL SPTD MW, SIP 894-850#, FP 77-99 / 99-143#
DST (4) 3588-3608 (LKC 70' ZN) / 30-30-30-30, 300' GIP, REC
60' OCWM, 180' MDY OIL, SIP 732-710#, FP 55-77 / 110-132#
DST (5) 3714-3764 (LKC 200 & 220' ZNS) / 30-45-30-45, REC
80' HMCO, SIP 1164-1131#, FP 77-77 / 77-88#
MCT - CO, PF (LKC) 3723-26, 3730-34, 3602-04.5, W/ 2 SPF,
AC 1500G, SWB DWN, GSO, T&R, POP. P 30 BO & 50 BWPD 2/
24/84

COPYRIGHT 1983
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS