

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-153-20498-00-02
Spot: N2NWNENW Sec/Twnshp/Rge: 9-1S-34W
320 feet from N Section Line, 1650 feet from W Section Line
Lease Name: TEXACO-CAHOJ UNIT Well #: 902
County: RAWLINS Total Vertical Depth: 3699 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N. WATER, STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4075		
PROD	5.5	4345	0	695 SX CMT
RBP		4055		
SURF	8.625	334	0	190 SX CMT

#120²²

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/23/2006 10:30 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: JOHN TURNER Company: MURFIN DRILLING CO., INC. Phone: (785) 462-1031

Proposed Plugging Method: Ordered 350 sxs Midcon II cement and 1000# hulls.
Plug through tubing.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/23/2006 2:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface casing set at 334' w/190 sxs cement.
5 1/2" production casing set at 4345' w/695 sxs cement.
PBTD 4075'. CIBP, TD 4348'.
Production casing had holes.
Ran tubing to 2500' - pumped 115 sxs cement with 400# hulls.
Pulled tubing to 1250' - pumped 75 sxs cement with 300# hulls.
Pulled tubing to 600' - pumped 60 sxs cement with 200# hulls. Cement to surface.
Pulled tubing to surface. Connected to 5 1/2" production casing - pumped 60 sxs cement with 100# hulls.
Max. P.S.I. 800#. S.I.P. 0#.
Connected to 8 5/8" surface pipe - pumped 15 sxs cement.
Max. P.S.I. 300#. S.I.P. 275#.

Perfs:

Top	Bot	Thru	Comments
4247	4249		
4213	4215		
4205	4210		
4182	4184		
4164	4169		
4084	4087		
4024	4032		
4008	4013		

RECEIVED
FEB 01 2006
KCC WICHITA

Remarks: SWIFT SERVICES, INC. #9129.

Plugged through: TBG

District: 04

Signed Darrel Dipman
INVOICED (TECHNICIAN)

DATE 2-2-06
INV. NO. 2006061051

JAN 24 2006

GETTY OIL COMPANY
 2705 VINE STREET, UNIT #4 #902 CAHOJ UNIT 9-1-34W
 HAYS, KS 67601 320'FNL&
 CONTR MURFIN DRILLING CTY RAWLINS 1650'FWL, NW/4
 GEOL _____ FIELD CAHOJ
 ELV 3118 KB SPD 11/23/83 CARD ISSUED 3/1/84 IP P 7 BO & 299 BWPD
 API 15-153-20,498 LKC 4008-4249 OA

+	+
+	+

LOG	Tops	Depth/Datum
ANH	2964 +	154
TOP	3814-	696
OREAD	3900-	782
DOUG	3973-	855
LANS	4007-	889
RTD	4348-	1230

8 5/8 " 334 / 190SX; 5 1/2 " 4345
 NO DSTS
 MICT - CO, PF (LKC) 4247-49, 4213-15, 4205-10, 4182-84,
 4164-69, 4084-87, 4024-32, 4008-13, AC 6500 G, SWB LD, SO,
 R & T, POP, P 7 BO & 299 BWP, 2/17/84

COPYRIGHT 1983
 INDEPENDENT OIL & GAS SERVICE, INC.
 WICHITA, KANSAS

153-20,498
 153-20,498
 153-20,498