

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-21641-00-00
Spot: SWNWNE Sec/Twnshp/Rge: 13-10S-18W
4290 feet from S Section Line, 2310 feet from E Section Line
Lease Name: JACO Well #: 2
County: ROOKS Total Vertical Depth: 3800 feet

Operator License No.: 32278
Op Name: TENGASCO, INC.
Address: 1327 NOOSE ROAD PO BOX 458
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3777	0	w/200 sxs cmt
SURF	8.625	286	0	w/180 sxs cmt

50
#123

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/30/2006 10:00 AM
Plug Co. License No.: 33369 Plug Co. Name: XTREME WELL SERVICE, INC.
Proposal Rcvd. from: GARY WAGNER Company: TENGASCO, INC. Phone: (785) 625-6374

Proposed Plugging Method: Ordered out 200 sxs 60/40 pozmix - 10% gel - 200# hulls.
DV at 1492' w/500 sxs. TOF at 3500' - left 7 joints tubing in the hole.
Emergency plug with rig over the hole.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/30/2006 1:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

TIH with tubing to 3300' - mixed and pumped 80 sxs cement with 200# hulls.
Pulled up to 1700' - circulated cement up 4 1/2" w/65 sxs cement.
POOH. Topped with 15 sxs.
Hooked up to the annulus and pumped 10 sxs cement.
S.I.P. 500#.

Perfs:

RECEIVED
FEB 03 2006
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

Jay Pfeifer

(TECHNICIAN)

INVOICED

DATE 2-3-06

INV. NO 2006061062

Form CP-2/3

JAN 31 2006

FRONTIER OIL CO. 13-10-18W
 1720 KS STATE BANK BLDG. #2 JACO SW NW NE
 WICHITA, KS 67202
 CONTR RED TIGER DRLG. CTY ROOKS

GEOLOGICAL JOEL A ALBERTS FIELD PLAINVILLE

E 2167 KB CM 4/6/82 CARD ISSUED 7/8/82 IP OIL WELL

LKC 3515-46 OA

+	+	+
+	+	+

API 15-163-21,641

SMP	TOPS	DEPTH	DATUM
ANH		1490	+ 677
B ANH		1526	+ 641
BRNVLE		2825	- 658
TARK		2924	- 757
HOW		3094	- 927
TOP		3122	- 955
HEEB		3343	-1176
TOR		3362	-1195
LKC		3386	-1219
BKC		3648	-1481
CONG		3655	-1488
CHT CONG		3662	-1495
SIMP DOL		3723	-1556
ARB		3745	-1578
RTD		3800	-1633
NO LOG			

8-5/8" 286/180sx, 4 1/2" 3777/200sx
 DV TOOL 1492/500sx
 DST (1) 3342-3458(TOR, LANS)/60-30-60-30
 180' M, SIP 1310-1210#, FP 20-30/
 30-40#
 DST (2) 3456-3506(LKC)/60-30-0-0, 75'
 M (PLUGGING ACTION), ISIP 1490#,
 IFP 30-60#
 DST (3) 3502-33(LKC)/60-30-60-30,
 60' GIP, REC 180' HO&GCM, SIP 1430-
 1390#, FP 51-81/81-112#
 DST (4) 3533-53(LKC)/60-30-30-30, 60'
 GIP, REC 30' SO&GCM, 10' HO&GCM,
 SIP 254-254#, FP 51-62/61-81#

(OVER)

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

111011