

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-22865-00-00
Spot: NWNENW Sec/Twnshp/Rge: 33-18S-11W
4950 feet from S Section Line, 3630 feet from E Section Line
Lease Name: PFAFF Well #: 5
County: BARTON Total Vertical Depth: 3420 feet

Operator License No.: 7383
Op Name: BOLDING, GRADY CORPORATION
Address: PO BOX 486
ELLINWOOD, KS 67526

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3419	0	100 SX CMT
SURF	8.625	258	0	225 SX CMT

111¹⁵

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/30/2006 9:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: GRADY BOLDING Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: Ordered 225 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/30/2006 11:45 AM KCC Agent: PAT STAAB

Actual Plugging Report:

Kelso sanded off bottom perfs to 3200' and topped with 5 sxs cement.
Mike's Testing cut off casing at 1693' and pulled to 1326'.
Allied rigged to casing and pumped 90 sxs 60/40 pozmix with 200# hulls mixed in.
Pulled casing to 575'. Allied rigged to casing and pumped 40 sxs cement with 200# hulls mixed in.
Pulled casing to 350'. Allied rigged to casing and pumped 70 sxs cement with 100# hulls mixed in.
Cement circulated to pit.
POOH. Pulled rest of casing - hole standing full.

Perfs:

Top	Bot	Thru	Comments
3353	3355		
3334	3338		

RECEIVED
FEB 03 2006
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #33553.

Plugged through: CSG

District: 04

Signed Pat Staab
(TECHNICIAN)

160

INVOICED
DATE 2-3-06
INV NO 200606065.9

JAN 31 2006

ISERN-SCHULTZ OIL & GAS, INC.

BOX 486

ELLINWOOD, KS 67526

CONTR WOODMAN & IANNITTI DRLG. CTY BARTON

#5 PFAFF 'TWIN'

¹⁸
33-19-11W
50'E.

C NW NE NW

GEOL _____ FIELD ELLINWOOD NORTH

E 1786 KB CM 8/3/82 CARD ISSUED 1/6/83 IP P 5 BO & 100 BWPD
ARB 3334-3355 OA

API 15-009-22,865

+	+	+
+	+	+
+	+	+

LOG	Tops	Depth/Datum
HEEB		2915-1129
TOR		2933-1147
DOUG		2947-1161
BR LM		3037-1251
LANS		3057-1271
BKC		3304-1518
ARB		3317-1531
TD		3420-1634

8 5/8 " 258/222SX, 5 1/2 " 3419/100SX
 DST (1) 3324-3343 (ARB) / 45-45-45-45, REC 50' OCM, 62'
 OCM, SIP 1047-1047#, FP 29-49 / 55-55#
 MICT - CO, PF (ARB) 3353-3355 & 3334-3338 W/4 SPF, AC
 350G, SWB LD, SO, POP, P 5 BO & 100 BWP, 10/10/82

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS