

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-095-22015-00-00  
Spot: W2W2E2SE Sec/Twnshp/Rge: 17-30S-5W  
1320 feet from S Section Line, 1050 feet from E Section Line  
Lease Name: THORNE Well #: 1  
County: KINGMAN Total Vertical Depth: 4735 feet

Operator License No.: 33168  
Op Name: WOOLSEY OPERATING COMPANY, LL  
Address: 125 N. MARKET, SUITE 1000  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	260		

# 153<sup>89</sup>

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/23/2005 1:15 AM  
Plug Co. License No.: 5929 Plug Co. Name: DUKE DRILLING CO., INC.  
Proposal Rcvd. from: JOHN ARMBRUSTER Company: DUKE DRILLING CO., INC. Phone: (316) 267-1331

Proposed  
Plugging  
Method:

35 sxs @ 4690'; 35 sxs @ 975'; 35 sxs @ 625'; 35 sxs @ 310'; 25 sxs @ 60'; and 15 sxs in rathole.

Plugging Proposal Received By: GREG EVES WitnessType: NONE  
Date/Time Plugging Completed: 12/23/2005 9:30 AM KCC Agent: GREG EVES

Actual Plugging Report:

Pumped 35 sacks of cement through drill pipe at 4690'. Pulled drill pipe to 975' and pumped 35 sacks of cement. Pulled drill pipe to 625' and pumped 35 sacks of cement. Pulled drill pipe to 310' and pumped 35 sacks of cement. Pulled drill pipe to 60' and circulated cement to surface. Pumped 15 sacks of cement in the rathole.

180sxs total of 60/40 posmix with 4% gel

Allied Cement #23035

Perfs:

RECEIVED  
KCC DISTRICT #2  
JAN 12 2006  
WICHITA, KS

RECEIVED  
JAN 31 2006  
KCC WICHITA

Remarks:

Plugged through: DP

District: 02

Signed

Greg Eves

(TECHNICIAN)

INVOICED

DATE 1-31-06

INV. NO 2006061035