

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-06660-00-00
Spot: SENENE Sec/Twnshp/Rge: 35-19S-6W
4290 feet from S Section Line, 330 feet from E Section Line
Lease Name: SMYRES Well #: 1
County: RICE Total Vertical Depth: 3339 feet

Operator License No.: 5610
Op Name: BRUCE OIL COMPANY, L.L.C.
Address: 1704 LIMESTONE RD.
MCPHERSON, KS 67460

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3338		
SURF	8.625	213		

\$108⁵²

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/10/2006 1:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 786-2001

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: PARTIAL
Date/Time Plugging Completed: 01/10/2006 2:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Sanded perforations to 3220' and capped with 5 sacks of cement. Cut off casing at 2210'. Pulled casing to 850' and pumped 35 sacks of cement with 100 lbs of cotton hulls. Pulled casing to 450' and pumped 35 sacks of cement with 100 lbs of cotton hulls. Pulled casing to 265' and and circulated cement to surface.

60/40 posmix with 4% gel

Allied Cement #24746

Perfs:

RECEIVED
KCC DISTRICT #2
JAN 13 2006
WICHITA, KS

RECEIVED
FEB 01 2006
KCC WICHITA

Remarks:

Plugged through: CSG

District: 02

Signed Virgil Clothier
(TECHNICIAN)

INVOICED
DATE 2-2-06
TEL. NO. 20060661076