

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-30092-00-00
Spot: SWSESW Sec/Twnshp/Rge: 32-18S-7W
549 feet from S Section Line, 3344 feet from E Section Line
Lease Name: NICHOLS Well #: 1
County: RICE Total Vertical Depth: 3330 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S. MARKET
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3329		120 sxs cement
SURF	8.625	314		

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/11/2006 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: See actual report.

RECEIVED
KCC DISTRICT #2
JAN 17 2006
WICHITA, KS

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/11/2006 1:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU - blew gas down. Pumped 35 sacks of cement with calcium chloride and 200 lbs of cotton hulls to bottom and displaced with water. Shut in well to allow cement to set. Perforated at 1050', 700', and 364'. Ran tubing to 1050' and pumped 35 sacks of cement with 100 lbs of cotton hulls. Pulled tubing to 700' and pumped 35 sacks of cement with 100 lbs of cotton hulls. Pulled tubing to 364' and circulated cement to surface.

60/40 posmix with 4% gel

United Cement #6748

Perfs:

Top	Bot	Thru	Comments
3246	3260		250-275 sxs cement

RECEIVED
FEB 01 2006
KCC WICHITA

Remarks: CONTROL #2005-0025-001

Plugged through: TBG

District: 02

Signed Virgil Clothier
(TECHNICIAN)