

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-25486-00-00
Spot: NWSENE Sec/Twnshp/Rge: 17-14S-17W
1725 feet from N Section Line, 1025 feet from E Section Line
Lease Name: PFEIFER Well #: 2
County: ELLIS Total Vertical Depth: 3605 feet

Operator License No.: 33625
Op Name: HERTEL OIL COMPANY LLC
Address: 704 EAST 12TH ST.
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	206		

#117¹⁶

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 01/20/2006 8:00 PM
Plug Co. License No.: 33237 Plug Co. Name: ANDERSON, C. D. DBA ANDERSON DRILLING
Proposal Rcvd. from: DARRELL ANDERSON Company: ANDERSON, C. D. DBA ANDERSON Phone: (785) 421-2234

Proposed Plugging Method: Order 215 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: HERB DEINES Witness Type: NONE
Date/Time Plugging Completed: 01/20/2006 10:00 PM KCC Agent: HERB DEINES

Actual Plugging Report:


1st. Plug at 3512' w/25 sxs.
2nd. Plug at 1225' w/25 sxs.
3rd. Plug at 725' w/100 sxs.
4th. Plug at 260' w/40 sxs.
5th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.

Perfs: RECEIVED
FEB 03 2006
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed 

(TECHNICIAN)
INVOICED

DATE 2.3.06
INV. NO. 2006061060

Form CP-2/3

FEB 02 2006