

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-155-21498-00-00
Spot: W2SWSESW Sec/Twnshp/Rge: 3-23S-10W
400 feet from S Section Line, 1410 feet from W Section Line
Lease Name: KSU Well #: 1-3
County: RENO Total Vertical Depth: 3780 feet

Operator License No.: 9855
Op Name: GRAND MESA OPERATING COMPANY
Address: 200 E. 1ST STREET N. STE 307 FRMRS
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	210		

#122⁸⁵

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 01/12/2006 4:00 PM
Plug Co. License No.: 5142 Plug Co. Name: STERLING DRILLING COMPANY
Proposal Rcvd. from: LONNY STOVALL Company: GRAND MESA OPERATING COMP Phone: _____

Proposed Plugging Method: 35 sxs @ 1400'; 35 sxs @ 900'; 35 sxs @ 270'; 25 sxs @ 60'; and 15 sxs in rathole.

RECEIVED
KCC DISTRICT #2
JAN 17 2006
WICHITA, KS

Plugging Proposal Received By: STEVE VANGIESON WitnessType: NONE
Date/Time Plugging Completed: 01/12/2006 6:15 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

The drill pipe was run open to 1400' and 35 sacks of cement was spotted. The drill pipe was pulled to 900' and 35 sacks of cement was spotted. The drill pipe was pulled to 270' and 35 sacks of cement was spotted. The drill pipe was pulled to 60' and 25 sacks of cement was circulated to surface. The rathole was circulated with 15 sacks of cement.

60/40 posmix with 4% gel

Acid Services #10376

Perfs:


RECEIVED
JAN 31 2006
KCC WICHITA

Remarks:

Plugged through: DP

District: 02

Signed



(TECHNICIAN)

INVOICED

DATE

1-31-06

INV. NO

2006061034