

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-20297-00-00
Spot: NESESE Sec/Twnshp/Rge: 5-22S-14W
990 feet from S Section Line, 330 feet from E Section Line
Lease Name: MORRISON-LONG A Well #: 4
County: STAFFORD Total Vertical Depth: 3865 feet

Operator License No.: 30681
Op Name: HOFFMAN OIL, INC.
Address: 18368 LAWRENCE 2100
MOUNT VERNON, MO 65712

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3860	0	WITH 100 SX CMT
SURF	8.625	466		WITH 375 SX CMT

#125^{bl}

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/12/2006 11:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING REPORT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/12/2006 2:50 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

COMPANY ATTEMPTED TO CLEAN OUT HOLE. COULD NOT GET PAST 837'. RAN TUBING TO 835'. PUMPED 435 SX CMT DOWN TUBING. GOOD CIRCULATION UP 8 5/8" X 4 1/2" ANNULUS & 4 1/2". NO SHOW OF CMT. PULLED TUBING TO 450'. PUMPED 225 SX CMT DOWN TUBING. CIRCULATED CMT TO SURFACE UP 4 1/2" & 8 5/8" X 4 1/2" ANNULUS. PULLED TUBING OUT OF HOLE. TOPPED OFF HOLE WITH 50 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3860	3865	OH	


RECEIVED
FEB 06 2006

Remarks: USED 60/40 POZMIX 6% GEL BY COPELAND.

Plugged through: TBG

KCC WICHITA

District: 01



Signed

Richard W. Lacy

(TECHNICIAN)

INVOICED

DATE 2-7-06
INV. NO. 2006061072

Form C-12