

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-195-22308-00-00  
Spot: NWSWNW Sec/Twnshp/Rge: 13-11S-24W  
1485 feet from N Section Line, 495 feet from W Section Line  
Lease Name: GALEN GEYER WL Well #: 1  
County: TREGO Total Vertical Depth: 4020 feet

Operator License No.: 33657  
Op Name: OHIO KENTUCKY OIL CORPORATION  
Address: THE WILLIAM M. GRIFFITH BUILDING  
LEXINGTON, KY 40503

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	211		

# 130<sup>65</sup>

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/27/2005 6:00 AM  
Plug Co. License No.: 33493 Plug Co. Name: AMERICAN EAGLE DRILLING LLC  
Proposal Rcvd. from: DON Company: AMERICAN EAGLE DRILLING LLC Phone: (303) 722-2899

Proposed Plugging Method: Order 190 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: HERB DEINES Witness Type: NONE  
Date/Time Plugging Completed: 10/27/2005 7:00 AM KCC Agent: HERB DEINES

Actual Plugging Report:

1st. Plug at 2000' w/25 sxs.  
2nd. Plug at 1175' w/100 sxs.  
3rd. Plug at 275' w/40 sxs.  
4th. Plug at 40' w/10 sxs.  
Rathole with 15 sxs.


Perfs:

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

RECEIVED  
FEB 6 2006  
KCC WICHITA

District: 04

Signed   
(TECHNICIAN)

INVOICED

DATE 2-7-06  
INV. NO. 2006061075

FEB 03 2006