

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-185-22340-00-01  
Spot: S2 Sec/Twnshp/Rge: 1-24S-11W  
1320 feet from S Section Line, 2640 feet from E Section Line  
Lease Name: ZENITH WATERFLOOD UNIT Well #: 35  
County: STAFFORD Total Vertical Depth: 3818 feet

Operator License No.: 32699  
Op Name: ZU, LLC  
Address: 108 WEST 34TH  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
L1	3.5	3757		
PROD	5.5	3817	0	WITH 175 SX CMT
SURF	8.625	212		WITH 150 SX CMT

#124<sup>09</sup>

Well Type: EOR UIC Docket No: E12893.15 Date/Time to Plug: 01/25/2006 9:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: GREG WHITEHAIR Company: ZU, LLC Phone: (785) 432-0789

Proposed Plugging Method: RUN IN WITH TUBING TO 3600', SPOT 40 SX OF 60/40 W/6% GLE, ONE BAG OF CALCIUM AND 300# COTTONSEED HULLS ON BOTOM. WAIT ONE HOUR PRESSURE UP CSG TO 200 PSI, IF IT HOLDS THEN PERF @ 550' ONE FOOT 4 SPF, THEN TRY TO CIRCULATE CMT TO SURFACE ON BACKSIDE AND FILL CSG WITH CMT. IF IT DOES NOT HOLD HOLD THEN SPOT CMT @ 690', WAIT ONE HOUR AND FINISH PLUGGING.

Plugging Proposal Received By: STEVE DURRANT Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 01/25/2006 4:08 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

ANHYDRITE = 550'. RAN TUBING TO 3570'. SPOTTED 40 SX 60/40 POZMIX 6% GEL 3% CC. PULLED TUBING. PRESSURE TEST 3 1/2" TO 250 PSIG. PRESSURE HELD. PERFORATED 3 1/2" X 5 1/2" @ 550'. PUMPED DOWN 3 1/2" WITH 50 SX CMT. CIRCULATED CMT UP 3 1/2" X 5 1/2" ANNULUS. SHUT IN 3 1/2" X 5 1/2" ANNULUS. PRESSURED TO 700 PSIG. PUMPED DOWN 8 5/8" X 5 1/2" ANNULUS WITH 85 SX CMT. MAXIMUM PRESSURE 600PSIG. SHUT IN PRESSURE 400 PSIG.

Perfs:

Top	Bot	Thru	Comments
3703	3717		

RECEIVED  
FEB 6 2006  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED.

Plugged through: TBG

District: 01

RECEIVED  
FEB - 1 2006  
KCC Dodge City

Signed Richard W. Lacey  
(TECHNICIAN)

INVOICED  
DATE 2-7-06  
INV. NO. 2006061085

Form SP-23