

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-097-21135-00-00
Spot: S2NESWNE Sec/Twnshp/Rge: 27-29S-18W
3360 feet from S Section Line, 1650 feet from E Section Line
Lease Name: HIEBSCH Well #: 2
County: KIOWA Total Vertical Depth: 4989 feet

Operator License No.: 5004
Op Name: VINCENT OIL CORPORATION
Address: 125 N. MARKET, STE 1075
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	4989	3120	WITH 100 SX CMT
SURF	8.625	518		WITH 200 SX CMT #16214

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/31/2006 4:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 786-2001

Proposed Plugging Method: SAND OFF TO 4770' WITH 4 SX CMT. PLUG AT 1200' WITH 10 SX GEL & 50 SX CMT. PLUG AT 530' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: JIM HOLLAND WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/31/2006 5:30 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SANDED BACK TO 4770' & PUT 4 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. SPOT PLUGS THROUGH CASING. 1ST PLUG @ 1200' WITH 12 SX GEL & 50 SX CMT. 2ND PLUG AT 530' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:


Top	Bot	Thru	Comments
4819	4824		

RECEIVED
FEB 06 2006
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED.

Plugged through: CSG

District: 01



Signed

Stephen J. Pfeifer
(TECHNICIAN)

INVOICED

DATE 2-7-06

INV. NO. 2006061081

Form CP 213