

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-22843-00-00
Spot: NESWSW Sec/Twnshp/Rge: 32-16S-23W
990 feet from S Section Line, 4290 feet from E Section Line
Lease Name: MISHLER L Well #: 1
County: NESS Total Vertical Depth: 4540 feet

Operator License No.: 33593
Op Name: BARRACUDA OPERATING COMPANY
Address: PO BOX 405
NESS CITY, KS 67560

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|-----------------|
| DVT | | 1600 | | WITH 425 SX CMT |
| PROD | 5.5 | 4539 | 0 | WITH 625 SX CMT |
| SURF | 8.625 | 248 | | WITH 150 SX CMT |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/25/2006 10:45 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: JIM WEIGHOUS Company: ALLIED CEMENT COMPANY Phone: (620) 793-5861

Proposed Plugging Method: PUMP 400# HULLS & 25 SX CMT & MUD TO 1600'. CMT TO 0'. USE 50 SX CMT TO CHECK ANNULUS.

Plugging Proposal Received By: STEVE DURRANT Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/25/2006 11:45 AM KCC Agent: JERRY W. STAPLETON

Actual Plugging Report:

PUMP 50# HULLS AHEAD OF 25 SX CMT WITH 50# HULLS FOLLOWED BY 28 SX GEL TO 1600'. PUMP 200# HULLS WITH 125 SX CMT. PRESSURED TO 1400#. SHUT IN AT 1100#. PUMPED 10 SX CMT DOWN ANNULUS. PRESSURED TO 400#.

Perfs:


| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 4498 | 4500 | | |

RECEIVED
FEB 06 2006
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED.

Plugged through: CSG

District: 01



Signed

Jerry W. Stapleton (TECHNICIAN) PART II

INVOICED

DATE 2-7-06

TEL NO. 2006061066

Form CR-2