

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-165-20912-00-00  
Spot: NESENW Sec/Twnshp/Rge: 14-16S-20W  
3630 feet from S Section Line, 2970 feet from E Section Line  
Lease Name: MORAN Well #: 1  
County: RUSH Total Vertical Depth: 3919 feet

Operator License No.: 5042  
Op Name: EDMISTON OIL COMPANY, INC.  
Address: 125 N. MARKET, STE 1130  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3918	0	WITH 220 SX CMT
SURF	8.625	447		WITH 325 SX CMT

#127 37

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/18/2006 10:00 AM  
Plug Co. License No.: 5042 Plug Co. Name: EDMISTON OIL COMPANY, INC.  
Proposal Rcvd. from: DALE MAY Company: EDMISTON OIL COMPANY, INC. Phone: (316) 265-5241

Proposed Plugging Method: RUN TUBING TO 3550'. PUMP 200# HULLS & 50 SX CMT. PERFORATE AT 1000'. CIRCULATE TO SURFACE.

Plugging Proposal Received By: JIM HOLLAND Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 01/18/2006 1:40 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

COMPANY ATTEMPTED TO CLEAN OUT HOLE FOR 3 DAYS. COULD NOT GET PAST 1223'. LEFT BIT IN HOLE @ 1223'. PERFORATED AT 900'. PUMPED 50 SX 60/40 POZMIX 6% GEL 3% CC DOWN TUBING AT 1160'. GOOD CIRCULATION UP 4 1/2". PULLED TUBING TO 900'. PUMPED 55 SX CMT DOWN TUBING. CIRCULATED CMT TO SURFACE UP 4 1/2". SHUT IN 4 1/2". PUMPED 50 SX CMT OUT & LOSS CIRCULATION ON 8 5/8" X 4 1/2" ANNULUS. PULLED TUBING. PUMPED 75 SX CMT DOWN 8 5/8" X 4 1/2" ANNULUS. MAXIMUM PRESSURE 350#. SHUT IN PRESSURE 300#.

Perfs:


Top	Bot	Thru	Comments
3900	3904		
3565	3568		

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED.

Plugged through: TBG

KCC WICHITA

District: 01



Signed

Richard W. Lacey  
(TECHNICIAN)

INVOICED

DATE 2-7-06  
INV. NO. 200606106A

Form CP-200