

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
30 S. Market, Room 2078  
Wichita, Kansas 67202

**Well Plugging Record**  
**K.A.R. -82-3-117**

API NUMBER 15-175-22028-00-00  
LEASE NAME Grant 'A'  
WELL NUMBER 1-5

TYPE OR PRINT  
NOTICE: Fill out completely and return  
to Cons. Div. office within 30 days.

330 Ft. from North Line of Section  
1980 Ft. from West Line of Section

LEASE OPERATOR McCoy Petroleum Corporation SPOT LOCATION N/2 Ne Nw  
ADDRESS 8080 E. Central, Suite 300 Section 5 Township 31s Range 31w  
CITY, STATE, ZIP Wichita, Kansas 67278-020867206 County Seward  
PHONE # 316-636-2737 Date Well Completed 01/28/06  
Character of Well Dry and Abandoned Date Plugging Commenced 01/28/06  
(Oil, Gas, D&A, SWD, Input, Water Supply Well) Date Plugging Completed 01/28/06

The plugging proposal was approved on January 28, 2006 (date)  
by Eric Maclaren (KCC District Agent's Name)

Is ACO-1 Filed? ? If not, is well log attached? Yes  
Producing Formation(s) D&A Depth to Top Bottom T.D. 5560

Show depth and thickness of all water, oil and gas formations.

**OIL, GAS OR WATER RECORDS**

**CASING RECORD**

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
Surface Soil, Sands and Clay		0	600	8-5/8"		
Sands and Clays		600	1858'	8-5/8"	1840'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

Plugging orders received from Eric Maclaren on 01/28/06. Bottom plug at 3350' w/ 100 sx;  
2nd plug at 1880' w/ 50 sx; 3rd plug at 600' w/ 50 sx; Top plug at 60' w/ 20 sx. All plugs  
60/40 Poz, 6% Gel. Plugged rathole with 15 sk, mousehole 10sx. Job complete 6:15 pm  
on 01/28/06. Acid Services ticket # 10381. Sterling reported plugging to KCC on 01/30/06.

Name of Plugging Contractor Sterling Drilling Company  
Licence No. 5142  
Address P.O. Box 1006 City: Pratt State: Kansas Zip 67124  
NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: McCoy Petroleum Corporation (Operator)

STATE OF KANSAS COUNTY OF PRATT, ss.

Gary M. Talbott, Agent (Employee of Operator or (Operator) of above described well, being first  
duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of  
the above described well as filed that the same are true and correct, so help me God.

(Signature) *Gary M. Talbott*  
(Gary M. Talbott, Vice-President of Sterling Drilling Company)

(Address) P.O. Box 1006 City: Pratt State: Kansas Zip 67124

SUBSCRIBED AND SWORN TO me this 2nd day of February, 2006

*Pamela S. Fields*  
(Notary Public)  
NOTARY PUBLIC - State of Kansas  
PAMELA S. FIELDS  
My Appt. Exp. 1-28-09

My Commission Expires: \_\_\_\_\_

Form CP-4  
Revised 12-92

*Bm*

RECEIVED  
FEB 6 2006  
KCC WICHITA

# Sterling Drilling Company, Rig #2

Box 1006, Pratt, Kansas 67124-1006  
Office Phone (620) 672-9508, Fax 672-9509

## SAMPLE LOG

Grant 'A' 1-5

**LOCATION:** N/2 Ne Nw Section 5 T 31s R 31w  
**API:** 15-175-22028-00-00 Seward County, Kansas

**OWNER:** McCoy Petroleum Corporation  
**CONTRACTOR:** Sterling Drilling Company, Rig #2

**COMMENCED:** 01/17/06  
**COMPLETED:** 01/28/06

**TOTAL DEPTH:** DRILLER 5560 FEET  
LOGGER 5548 FEET

**Ground Elevation:** 2824  
**KB Elevation:** 2835

## LOG

0 -	2 FEET	Top Soil
2 -	600 FEET	Surface Sands and Clay
600 -	1735 FEET	Clays, Sandstone and Shales
1735 -	1752 FEET	Anhydrite (Driller's)
1752 -	2620 FEET	Clays, Sandstone, Shales & Salt
2620 -	5560 FEET	Limestone/Shales

## CASING RECORDS

### Surface Casing:

Spud at 7:15 pm on 01/17/06. Drilled 12-1/4" hole to 1858'. Ran 46 joints of new 24# 8-5/8" surface casing tally 1840.32' set at 1852' KB. Welded straps on bottom 3 and top joints. Tacked collars on remainder. Cemented w/ 475 sx A-Con; 3% CC & 1/4# Cellflake/sx and 125 sx Class A w/ 2% C.C; 1/4 #/sx Celloflake. Cement did circulate. Plug down at 9:15 pm on 01/19/06. Acid Services ticket #10378.

### Production Casing:

Plugging orders received from Eric Maclaren on 01/28/06. Bottom plug at 3350' w/ 100 sx; 2nd plug at 1880' w/ 50 sx; 3rd plug at 600' w/ 50 sx; Top plug at 60' w/ 20 sx. All plugs 60/40 Poz, 6% Gel. Plugged rathole with 15 sk, mousehole 10sx. Job complete 6:15 pm on 01/28/06. Acid Services ticket # 10381. Sterling reported plugging to KCC on 01/30/06.

RECEIVED  
FEB 06 2006

KCC WICHITA

## DEVIATION SURVEYS

1 degree(s) at	1383	feet
3/4 degree(s) at	1858	feet
3/4 degree(s) at	4068	feet
1 degree(s) at	5560	feet