

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, Kansas 67202

Well Plugging Record
K.A.R. -82-3-117

API NUMBER 15-159-22477-0000
LEASE NAME Schartz
WELL NUMBER 1-30

TYPE OR PRINT

NOTICE: Fill out completely and return
to Cons. Div. office within 30 days.

230 Ft. from North Line of Section
1350 Ft. from West Line of Section

LEASE OPERATOR Gilbert-Stewart Operating LLC SPOT LOCATION 100' N & 30' E of N/2 N/2 Nw
ADDRESS 1801 Broadway, Suite 450 Section 30 Township 20s Range 10w
CITY, STATE, ZIP Denver, Colorado 80202 County Rice
PHONE # 303-534-1686 Date Well Completed 01/28/06
Character of Well Dry and Abandoned Date Plugging Commenced 01/28/06
(Oil, Gas, D&A, SWD, Input, Water Supply Well) Date Plugging Completed 01/28/06

The plugging proposal was approved on January 27, 2006 at 2:40 pm (date)
by Mike Wilson (KCC District Agent's Name)

Is ACO-1 Filed? ? If not, is well log attached? Yes
Producing Formation(s) D&A Depth to Top Bottom T.D. 3400

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PULL IN	PULL OUT
Surface Soil and Sands	Water sands	0	190			
Redbeds	Shale	190	325	8-5/8"	313'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Plugged well with heavy mud between plugs; 35 sx at 3300'; 35 sx at 1200'; 35 sx at 850'; 35 sx at 375' & 25 sx at 60' to surface. Plugged rathole with 15 sacks, no mousehole. Total cement used = 180 sx of 60/40 Poz with 4% Gel. Plugging completed at 1:15 am on 01/28/06. Allied Cementing ticket # 22478. Received plugging orders from Mike Wilson at 2:40 pm on 01/27/06. Sterling reported plugging to KCC on 01/30/06.

Name of Plugging Contractor Sterling Drilling Company
Licence No. 5142
Address P.O. Box 1006 City: Pratt State: Kansas Zip 67124
NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Gilbert-Stewart Operating LLC (Operator)

STATE OF KANSAS COUNTY OF PRATT, ss.

Gary M. Talbott, Agent (Employee of Operator or (Operator) of above described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed that the same are true and correct, so help me God.


(Signature) Gary M. Talbott
(Gary M. Talbott, Vice-President of Sterling Drilling Company)

RECEIVED
FEB 06 2006

KCC WICHITA

(Address) P.O. Box 1006 City: Pratt State: Kansas Zip 67124

SUBSCRIBED AND SWORN TO me this 2nd day of February, 2006



Pamela S. Fields
(Notary Public)

My Commission Expires: _____

[Handwritten mark]

Sterling Drilling Company, Rig #1

Box 1006, Pratt, Kansas 67124-1006
Office Phone (620) 672-9508, Fax 672-9509

SAMPLE LOG

Schartz 1-30

LOCATION: 100' N & 30' E of N/2 N/2 Nw
API: 15-159-22477-0000

Section 30 T 20s R 10w
Rice County, Kansas

OWNER: Gilbert-Stewart Operating LLC
CONTRACTOR: Sterling Drilling Company, Rig #1

COMMENCED: 20-Jan-06
COMPLETED: 29-Jan-06

TOTAL DEPTH: DRILLER 3400 FEET
LOGGER 3400 FEET

Ground Elevation: 1734
KB Elevation: 1743

LOG

0 -	3 FEET	Top Soil
3 -	190 FEET	Sands and Clays
190 -	435 FEET	Redbeds
435 -	451 FEET	Anhydrite
451 -	1390 FEET	Shales and Salt
1390 -	3300 FEET	Limestone, Shale and Dolomite
3300 -	3400 FEET	Arbuckle

CASING RECORDS

Surface Casing-8-5/8"

Spud at 8:15 pm on 01/20/06. Drilled 12-1/4" hole to 325'. Ran 8 joints of new 24#, 8-5/8" surface casing, tally 312.89' set at 322' KB. Cemented with 250 sx 60/40 Poz, 3% CC, 2% Gel. Cement did circulate. Plug down at 3:45 am on 01/21/06 by Allied Cementing, ticket # 24718. Welded straps on bottom 3 joints, welded collars on remaining joints.

Production Casing:

Plugged well with heavy mud between plugs; 35 sx at 3300'; 35 sx at 1200'; 35 sx at 850'; 35 sx at 375' & 25 sx at 60' to surface. Plugged rathole with 15 sacks, no mousehole. Total cement used = 180 sx of 60/40 Poz with 4% Gel. Plugging completed at 1:15 am on 01/28/06. Allied Cementing ticket # 22478. Received plugging orders from Mike Wilson at 2:40 pm on 01/27/06. Sterling reported plugging to KCC on 01/30/06.

DEVIATION SURVEYS

1/2	degree(s) at	325	feet	
3-1/2	degree(s) at	2850	feet	Taken on trip out for DST #3 at 3310'.
4-1/2	degree(s) at	3120	feet	
4	degree(s) at	3240	feet	
3-3/4	degree(s) at	3400	feet	

RECEIVED
FEB 6 2006
KCC WICHITA