

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, Kansas 67202

Well Plugging Record
K.A.R. -82-3-117

API NUMBER 15-007-22966-0000
LEASE NAME Landis Trust
WELL NUMBER A 1-21

TYPE OR PRINT

NOTICE: Fill out completely and return
to Cons. Div. office within 30 days.

2310 Ft. from North Line of Section
330 Ft. from East Line of Section

LEASE OPERATOR McCoy Petroleum Corporation SPOT LOCATION Se Se Ne
ADDRESS 8080 E. Central, Ste 300 Section 21 Township 32s Range 10w
CITY, STATE, ZIP Wichita, Kansas 67206 County Barber
PHONE # 316-636-2737 Date Well Completed 01/28/06
Character of Well Dry and Abandoned Date Plugging Commenced 01/28/06
(Oil, Gas, D&A, SWD, Input, Water Supply Well) Date Plugging Completed 01/28/06

The plugging proposal was approved on 01/27/06 (date)
by Eric Maclaren (KCC District Agent's Name)

Is ACO-1 Filed? ? If not, is well log attached? Yes
Producing Formation(s) D&A Depth to Top Bottom T.D. 4020

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
Surface Soil and Sands	Water sands	0	60			
Sand, Gravel and Clay	Shale	60	225	8-5/8"	211'	0'

2-7-06 4500 per Gary Talbot

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Plugging orders received from Eric Maclaren on 01/27/06. Bottom plug at 600' w/ 50 sx;
2nd plug at 250' w/ 40 sx; Top plug at 60' w/ 20 sx. Used 135 sx 60/40 Poz, 6% Gel.
Plugged rathole with 15 sk, mousehole 10sx. Job complete 12:30 pm on 01/28/06.
Acid Services ticket # 11913. Sterling reported plugging to KCC on 01/30/06.

Name of Plugging Contractor Sterling Drilling Company
Licence No. 5142
Address P.O. Box 1006 City: Pratt State: Kansas Zip 67124
NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: McCoy Petroleum Corporation (Operator)


STATE OF KANSAS COUNTY OF PRATT, ss.

Gary M. Talbot, Agent (Employee of Operator or (Operator) of above described well, being first
duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of
the above described well as filed that the same are true and correct, so help me God.

(Signature) *Gary M. Talbot*
(Gary M. Talbot, Vice- President of Sterling Drilling Company)
(Address) P.O. Box 1006 City: Pratt State: Kansas Zip 67124

SUBSCRIBED AND SWORN TO me this 2nd day of February, 2006

Pamela S. Fields
(Notary Public)



My Commission Expires: _____

B...

RECEIVED
FEB 6 2006
KCC WICHITA

Sterling Drilling Company, Rig #4

Box 1006, Pratt, Kansas 67124-1006
Office Phone (620) 672-9508, Fax 672-9509

SAMPLE LOG

Landis Trust A 1-21

LOCATION: Se Se Ne
API: 15-007-22966-0000

Section 21 T 32s R 10w
Barber County, Kansas

OWNER: McCoy Petroleum Corporation
CONTRACTOR: Sterling Drilling Company, Rig #4

COMMENCED: 01/19/06
COMPLETED: 01/28/06

TOTAL DEPTH: DRILLER 4820 FEET
LOGGER 4824 FEET

Ground Elevation: 1454
KB Elevation: 1463

LOG

0 -	3 FEET	Top Soil
3 -	12 FEET	Sand & Gravel
12 -	38 FEET	Clay
38 -	60 FEET	Sand & Gravel
60 -	1660 FEET	Shales and Salt
1660 -	4820 FEET	Limestone/Shales

CASING RECORDS

Surface Casing:

Spud at 2:15 pm on 01/19/06. Drilled 12-1/4" hole to 225'. Ran 5 jts. of new 23# 8-5/8" surface casing tallied 210.74' set at 221.74' KB. Cemented with 225 sx 60/40 Poz, 2% Gel, 3% CC & 1/4 # per sx Celloflake. Plug down at 9:15 pm on 01/19/06. Cement did circulate. Acid Services ticket # 11804. Welded straps on bottom 2 joints, welded collars on 3 joints.

Plugging Data:

Plugging orders received from Eric Maclaren on 01/27/06. Bottom plug at 600' w/ 50 sx; 2nd plug at 250' w/ 40 sx; Top plug at 60' w/ 20 sx. Used 135 sx 60/40 Poz, 6% Gel. Plugged rathole with 15 sk, mousehole 10sx. Job complete 12:30 pm on 01/28/06. Acid Services ticket # 11913. Sterling reported plugging to KCC on 01/30/06.

RECEIVED
FEB 26 2006

KCC WICHITA

DEVIATION SURVEYS

3/4 degree(s) at 225 feet
3/4 degree(s) at 4450 feet